
# **INDEX**

SHEET NO.	PLAN REFERENCE NO.	TITLE
1	IN1	INDEX
2	CT1	CERTIFICATION SHEET
3	VM1	VICINITY MAP
4	SQ1	SUMMARY OF QUANTITIES
5 - 7	DFD1 - DFD3	DEBRIS FLOW FENCE DETAIL
8 - 11	PMD1 - PMD4	PINNED WIRE MESH DETAIL
12 - 15	NA1 - NA4	SOIL PREPARATION
16 - 19	NB1 - NB4	PLANTING PLAN
20	CS1	CONSTRUCTION SIGNS CLASS A
21 - 22	TC1 - TC2	TRAFFIC CONTROL PLAN



NOTE: ALL SHEET REFERENCES, FIRST NOS. OF STRUCTURE CODE DESIGNATIONS AND MATCH LINE SHEET REFERENCES, ETC., THROUGHOUT THE PLANS, REFER TO THE ENTRY IN THE PLAN REFERENCE NUMBER BOX.

FILE NAME	G:\444302\03 - Design\D01421	1D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS	&E\22-	1 PS&E Transi	mittals, Reviews\Electronic Desi	gn Files\0001_XL6376_PS_IN_001	.dgn		Plot 1
TIME					REGION STATE	FED.AID PROJ.NO.			SR 14	PLAN REF. NO.
DATE					10 WASH	NHPP-0014(088)			1 MILE W OF SALMON FALLS RD	IN1
PLOTTED BY					IU WASH				REPAIR DEBRIS FENCE	""
DESIGNED BY	A. PIERCE				JOB NUMBER			Washington State Department of Transportation		SHEET
ENTERED BY	A. PIERCE				23X337			Washington State Department of Transportation	RE-ADVERTISEMENT	1 1
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.				OF
PROJ. ENGR.	M. BRIGGS					XL 6376	DATE		INDEX	22 SHEETS
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		XE 03/0	P.E. STAMP BOX			SHEETS

### PROJECT LICENSED PROFESSIONAL CERTIFICATES


Meter Noveger	Muful	mil 7. Cartot	
Mike Briggs	Marc Fish	Daniel R. Corlett	
Mar 16, 2023	Mar 16, 2023	Mar 21, 2023	
AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.
AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.
AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.	AS A PROFESSIONAL ENGINEER IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION AS A LICENSED PROFESSIONAL.

#### NOTES:

THIS PLAN SET WAS DEVELOPED ELECTRONICALLY UNDER THE DIRECT SUPERVISION OF THE LICENSED PROFESSIONALS THAT HAVE AFFIXED THEIR SIGNATURE TO THIS PAGE.

THIS SHEET SERVES AS THE CERTIFICATION BY THE ABOVE LICENSED PROFESSIONALS OF ALL SHEETS IN THIS PLAN SET WHERE THEIR STAMPS AND SIGNATURES APPEAR.

FILE NAME	G:\444302\03 - Design\D01421I	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\20-CAI	DD-Pla	ans\20-11 PS&E	Sheets\XL6376_PS_CT.dgn					Plot 1
TIME	11:11:18 AM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	2/2/2023				10 WASH	NHPP-0014(088)				1 MILE W OF SALMON FALLS RD	CT1
PLOTTED BY	piercea				I TO WASII	` ′					
DESIGNED BY	A. PIERCE				JOB NUMBER				Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	A. PIERCE				23X337				]	RE-ADVERTISEMENT	2
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.			Department of Transportation		OF !
PROJ. ENGR.	M. BRIGGS					XL 6376	— DATE	DATE		CERTIFICATE SHEET	22 SHEETS
REGIONAL ADM	. C. FRANCIS	REVISION	DATE	BY		XE 0370	P.E. STAMP BOX	P.E. STAMP BOX			SHEETS





## SUMMARY OF QUANTITIES

		SUB-TOTAL	SUB-TOTAL				GROUP 1	GROUP 2											
IITEM	TOTAL	* SECTION	** SECTION	STD.					+										
NO		I-07.2(1)	I-07.2(2)	ITEM	UNIT	ITEM	MP 25.35 TO MP 25.45	THIRD PARTY											( L
	QUANTITY	OF STANDARD	OF STANDARD	NO.				DAMAGES											ı
		SPECS	SPECS																( I
<del>  </del>		1		+		PREPARATION	<u> </u>	<u> </u>	+			1		1	<u> </u>	-			
	LUMP SUM		LLIMD SLIM	I 0001	1.0	MOBILIZATION	_	<u> </u>	1	<u>                                       </u>	<u> </u>	<u> </u> 		<u> </u> 	<u>                                     </u>	<del></del>			
╽╠╧┼	LUMP SUM		LOWIT SOW	1	L.J.	I		1	1	<u> </u>	<u>I</u>	<u> </u> 	<u> </u>	! 	<u>                                     </u>	<u> </u>	!		
<del>                                   </del>	ĺ			<del>                                     </del>		GRADING		1	1	<u> </u>		l	l	! 	l I	<del></del>			
	100.00		100.00	1 0310	CV	ROADWAY EXCAVATION INCL. HAUL		1	1					! 	l I	<u>_</u>		. <del></del>	
	100.00		100.00	1	0.1.		11 100.00	i	<del> </del>	1 1	i	<u> </u>		<u>.</u> İ	<u> </u>	<del></del>		,	
<del>                                   </del>				1		EROSION CONTROL AND ROADSIDE PLANTING	<u> </u>	i	1	1	1			İ	1	<del>-                                    </del>		-	
3	6.00		6.00	I 6403	DAY	ESC LEAD	6.00	İ	i	1 1	1	<u> </u>		İ	<u> </u>	<u> </u>	! 	<del> </del>	
	470.00		470.00			COMPOST BLANKET	470.00	i	i	<u> </u>	1	! 		i I	<u> </u>	<del></del>		<del> </del>	
5	10000.00		10000.00	6490		EROSION/WATER POLLUTION CONTROL	10,000.00	<u> </u>	<u> </u>	<u>.                                      </u>		! 		<u>.                                    </u>	<u> </u>	<u>_</u>		<del></del>	
6	470.00		470.00			SEEDING, FERTILIZING AND MULCHING	470.00	i i	i	<u> </u>	i	<u> </u>		<u>.                                    </u>	<u> </u>	i		. <del></del>	
	600.00		600.00	•		PREPARATION FOR PLANTING	600.00	i	<u> </u>	<u> </u>	1	! 		! 	<u> </u>	<del></del>		<del></del>	
8 1	10.00		10.00			PSIPE TREE MIX A	10.00	i	i	1 1	1	<u> </u>		İ	<u> </u>	<u> </u>	! 	<del> </del>	
9	550.00		550.00			PSIPE SHRUB MIX A	550.00	i i	i	<u> </u>	1	! 		<u>.                                    </u>	i i	<del>i</del>	i		
10	1400.00		1400.00			PSIPE GRASS MIX A	1,400.00	<u> </u>	<u> </u>	<u>.                                      </u>	1	! 		<u>.                                    </u>	<u> </u>	<u>_</u>		<del></del>	
11	1600.00		1600.00			PSIPE GRASS MIX B	1,600.00	i i	i	<u> </u>	i	<u> </u>		<u>.                                    </u>	<u> </u>	i		. <del></del>	
12	170.00		170.00	-		BARK OR WOOD CHIP MULCH	170.00	i	i	<u> </u>				<u>.</u> I		i			,
13	470.00		470.00	1		BIODEGRADABLE EROSION CONTROL BLANKET	470.00	i	i	I I	i			<u>.</u> İ	<u> </u>	i		, i	ı i
14	1700.00		1700.00	i		STRAW WATTLE	1,700.00	i	İ	i i	i			i	i i	i		i	<u> </u>
15	20.00		20.00	i		GENERAL WEED CONTROL - CHEMICAL APPLICATION	20.00	i	İ	i i	i			i	i i	i		i	ı i
16	20.00		20.00	i		GENERAL WEED CONTROL - HAND OR MECHANICAL	20.00	i	İ	i i				i i		i		i	<u> </u>
liti	Ì			i		İ	ii	i	İ	i i	i			i	i i	i	İ	i	i
liti				i		TRAFFIC	ii i	İ	İ	i i	i			İ	i i	i	i	i	
17	300.00		300.00	7448	HR	TRANSPORTABLE ATTENUATOR	300.00	İ	İ	i i	İ			İ	i i	i	i	i	<u> </u>
18	10000.00		10000.00	7450	DOL	REPAIR TRANSPORTABLE ATTENUATOR	10,000.00	İ	İ	i i	İ			ĺ	İ	i		i	
19	840.00		840.00	6993	HR	PORTABLE CHANGEABLE MESSAGE SIGN	840.00	İ	İ	i i	İ			İ	i i	ĺ		, i	
20	LUMP SUM		LUMP SUM	6973	L.S.	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	L.S.	İ	İ	i i	İ			ĺ	İ	ĺ		i	
21	480.00		480.00	6980	HR	FLAGGERS	480.00	İ		i i	İ			ĺ	İ	ĺ			
22	180.00		180.00	6992	HR	OTHER TRAFFIC CONTROL LABOR	180.00	1						1					i I
23	LUMP SUM		LUMP SUM	6974	L.S.	TRAFFIC CONTROL SUPERVISOR	L.S.	1	1		1			[					i I
24	25000.00		25000.00	7572	DOL	WORK ZONE SAFETY CONTINGENCY	25,000.00	1	1		1			1					i I
25	72.00		72.00	6982	S.F.	CONSTRUCTION SIGNS CLASS A	72.00	1	1					1					<u> </u>
								1	1	<u> </u>	1			<u> </u>					<u> </u>
						OTHER ITEMS										1			<u> </u>
26	10000.00		10000.00	7715	DOL	FORCE ACCOUNT VISUAL MITIGATION	10,000.00												<u>.                                    </u>
27	48000.00		48000.00			FORCE ACCOUNT ROCK DOWELS TYPE 1	48,000.00	1		<u> </u>				<u> </u>					
28	5000.00		5000.00	7715	DOL	FORCE ACCOUNT GROUT EXCEEDANCE	5,000.00	1	1	<u> </u>				<u> </u>					
29	10000.00		10000.00			ROADSIDE CLEANUP	10,000.00	<u> </u>						<u> </u>					<u> </u>
30	5.00		5.00			REIMBURSEMENT FOR THIRD PARTY DAMAGE		5.00						<u> </u>					
31	-1.00		-1.00			MINOR CHANGE	-1.00	<u> </u>	1	<u> </u>				<u> </u>					
32	-1.00		-1.00			AGGREGATE COMPLIANCE PRICE ADJUSTMENT	-1.00		1	<u> </u>									1
33	LUMP SUM		LUMP SUM	7736		SPCC PLAN	L.S.	<u> </u>	1	<u> </u>				<u> </u>					<u>.                                    </u>
34	3400.00		3400.00			PINNED WIRE MESH SLOPE STABILIZATION SYSTEM	3,400.00	<u> </u>	1					<u> </u>					<u>.                                    </u>
35	LUMP SUM		LUMP SUM		L.S.	REPLACE GEOBRUGG VX140 DEBRIS FLOW FENCE	L.S.	<u> </u>		<u> </u>									
							JI												<u>.                                    </u>

GROUP	GROUP NUMBER	SR	CONTROL SECTION	TAX SCHEDULE	FUND PARTICIPANTS
LEGEND	1	014	300136	**	FEDERAL,STATE
	2	014	300136	**	STATE

		REGION	STATE	FEDERAL AID PROJECT. NO.		SR 14	SQ1
		10	WA	NHPP-0014(088)			301
		'0	WA		Washington State	1 MILE W OF SALMON FALLS RD	SHEET
		JOB NU			Department of Transportation	REPAIR DEBRIS FENCE RE-ADVERTISEMENT	4
		23X3	337/3		Department of Transportation		OF
		CONTRA	ACT NO			SUMMARY OF QUANTITIES	22
DATE	REVISION BY	000	000				SHEETS





REGIONAL ADM. C. FRANCIS

RING NET WITH WIRE MESH BACKING

BORDER ROPE

WIRE ROPE ANCHOR

BRAKING ELEMENT

ABRASION PROTECTION

DEBRIS FLOW CHANNEL

- NOTE:
  1 Wire rope anchors shall have a minimum pullout strength per the debris flow fence manufacturer's specifications.
  2 Each support and border rope shall have a braking element as per the manufacturer's specifications.
  3 The wire mesh backing shall be placed on the downslope side of the ring nets.
  4 Number of support and border ropes as per the manufacturer's specifications.

### **DEBRIS FLOW FENCE DETAIL**

5.5.5									
FILE NAME	G:\444302\03 - Design\D01421	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS	&E\22-	1 PS&E Transi	mittals, Reviews\Electronic Desi	gn Files 10006 XL6376_PS_DFD_0	02.dgn	
TIME	9:31:03 AM				REGION STATE	FED.AID PROJ.NO.			
DATE	3/8/2023				10 WASH	NHPP-0014(088)			
PLOTTED BY	piercea				10 WASH				
DESIGNED BY	S. JOHNSTON				JOB NUMBER		Engineering Gyclogist		
ENTERED BY	A. PIERCE				23X337		Sized Geolog		l _
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.	Marc F. Fish		Depa
PROJ. ENGR.	M. BRIGGS					XL 6376	SEE SHEET CT1 DATE	DATE	
DEGIGNAL ARM	O EDANOIG	DEMICION	DATE	D)/	1	AL 03/0	I DATE	I DATE	1


DATE BY

REVISION

14/ 1: 4 04 4	SR 14 V OF SALMOI PAIR DEBRIS RE-ADVERTISEI

DFD2 ON FALLS RD **FENCE** MENT 22 SHEETS **DEBRIS FLOW FENCE DETAIL** 

Plot 2 PLAN REF NO




### DEBRIS FLOW FENCE DETAIL


#### NOTES

\*\* SHACKLES CAN BE REUSED IF IN GOOD CONDITION.

FILE NAME	G:\444302\03 - Design\D01421	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS	&E\22-1 PS&E Transı	nittals, Reviews\Electronic Desi	ign Files (1997) XL6376_PS_DFD_d	03.dgn			Plot 3
TIME	9:01:20 AM			REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	3/8/2023			10 WASH	NHPP-0014(088)				1 MILE W OF SALMON FALLS RD	DFD3
PLOTTED BY	piercea			I IU WASII	,					5, 53
DESIGNED BY	S. JOHNSTON			JOB NUMBER		Engineering Georgiss 2655		Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	A. PIERCE			23X337		Vsed Geolog		9	RE-ADVERTISEMENT	7
CHECKED BY	K. LEI			CONTRACT NO.	LOCATION NO.	Marc F. Fish		Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS				XL 6376	SEE SHEET CT1 DATE	DATE		DEBRIS FLOW FENCE DETAIL	22 SHEETS
REGIONAL ADM	C FRANCIS	REVISION	DATE	BY	XL 0310	DE STAMP BOY	DE STAMP BOY			SHEETS



FILE NAME	G:\444302\03 - Design\D01421	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS	S&E\22-1	1 PS&E Transı	mittals, Reviews\Electronic Des	ign Files 100008 XL6376_PS_PMD_0	01.dgn			Plot 7
TIME	11:50:50 AM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	3/14/2023			-	10 WASH	NHPP-0014(088)				1 MILE W OF SALMON FALLS RD	PMD1
PLOTTED BY	PierceA				IU WASH						' '''
DESIGNED BY	S. JOHNSTON				JOB NUMBER		Engineering Geologic		Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	A. PIERCE				23X337		Sed Geolog		1	RE-ADVERTISEMENT	8
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.	Marc F. Fish		Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS					XL 6376	SEE SHEET CT1	DATE	-	PINNED WIRE MESH DETAIL	22 SHEETS
REGIONAL ADM.	. C. FRANCIS	REVISION	DATE	BY		AE 0370	P.E. STAMP BOX	P.E. STAMP BOX			SHEETS



REGIONAL ADM. C. FRANCIS



### PINNED WIRE MESH DETAIL

#### NOTES

- TREES TO BE REMOVED BEYOND THE LIMITS OF THE DEBRIS CHUTE SHALL BE IDENTIFIED BY THE ENGINEER.
- THE BROW OF THE DEBRIS CHUTE SHALL BE ROUNDED TO ELIMINATE OVERHANGING MATERIAL PRIOR TO INSTALLATION OF EROSION CONTROL BLANKET. SEE SPECIAL PROVISIONS "ROADSIDE CLEANUP."

FILE NAME	G:\444302\03 - Design\D01421	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris F	Fence\22-PS&	&E\22-	1 PS&E	Transn	nittals, Reviews\Electronic Desi	gn Files 100009 XL6376_PS_PMD_0	02.dgn
TIME	11:57:07 AM				REGION	STATE	FED.AID PROJ.NO.		
DATE	3/14/2023				10	WASH	NHPP-0014(088)		
PLOTTED BY	PierceA				יי ן	WASH			
DESIGNED BY	S. JOHNSTON					IUMBER		Co. Segmeering Geologist 2655	
ENTERED BY	A. PIERCE				23X	(337		rsed Geold	
CHECKED BY	K. LEI				CONTE	RACT NO.	LOCATION NO.	Marc F. Fish	
PROJ. ENGR.	M. BRIGGS				ĺ		XL 6376	SEE SHEET CT1	——————————————————————————————————————
DECIONAL ADM	C EDANCIS	DEVISION	DATE	DV	1		VE 0310	DATE	BAIL

DATE BY


REVISION



	SR 14	
1 1	I MILE W OF SALMON FALLS	RD
	REPAIR DEBRIS FENCE	
	RE-ADVERTISEMENT	

PINNED WIRE MESH DETAIL

Plot 4 PLAN REF NO PMD2 22 SHEETS






PINNED WIRE MESH SYSTEM LIMITS

PINNED WIRE MESH SYSTEM GROUND ANCHORS

## PINNED WIRE MESH DETAIL

FILE NAME	G:\444302\03 - Design\D01421	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS	&E\22-	1 PS&E Transı	nittals, Reviews\Electronic Desi	gn Files 100719 XL6376_PS_PMD_0	03.dgn			Plot 5
TIME	12:03:09 PM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	3/14/2023				10 WASH	NHPP-0014(088)				1 MILE W OF SALMON FALLS RD	PMD3
PLOTTED BY	PierceA				10 WASH					REPAIR DEBRIS FENCE	1 14125
DESIGNED BY	S. JOHNSTON				JOB NUMBER		Engineering Geologis		Washington State		SHEET
ENTERED BY	A. PIERCE				23X337		Sed Geolog		1	RE-ADVERTISEMENT	10
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.	Marc F. Fish		Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS					XL 6376	SEE SHEET CT1 DATE	— DATE	-	PINNED WIRE MESH DETAIL	22 SHEETS
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		AE 3370	P.E. STAMP BOX	P.E. STAMP BOX			UNICE 18






PINNED WIRE MESH SYSTEM LIMITS




PINNED WIRE MESH SYSTEM GROUND ANCHORS

## PINNED WIRE MESH DETAIL

FILE NAME	G:\444302\03 - Design\D01421E	SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\22-PS8	&E\22-1	1 PS&E Trans	mittals, Reviews\Electronic Des	ign Files (0071 XL6376_PS_PMD_0	004.dgn			Plot 6
TIME	12:41:38 PM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	3/14/2023				10 WASH	NHPP-0014(088)				1 MILE W OF SALMON FALLS RD	PMD4
PLOTTED BY	PierceA				IU WASI	,					' ''''
DESIGNED BY	S. JOHNSTON				JOB NUMBER		Engineering Geology 2655		Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	A. PIERCE				23X337		Sed Geolog		, ,	RE-ADVERTISEMENT	1 11
CHECKED BY	K. LEI				CONTRACT NO.	LOCATION NO.	Marc F. Fish		Department of Transportation		_ OF
PROJ. ENGR.	M. BRIGGS					XL 6376	SEE SHEET CT1 DATE	DATE	-	PINNED WIRE MESH DETAIL	22 SHEETS
DECIONAL ADM	C EDANCIS	DEVISION	DATE	DV		/	DATE	DATE OF STREET			1 511213





#### CONSTRUCTION NOTES


- SURFACE PREPARATION PRIOR TO COMPOST BLANKET PLACEMENT. SMOOTH SLOPE SURFACE AS DIRECTED BY ENGINEER. REMOVE ALL LOOSE ROCKS, ROOTS, VEGETATION AND OTHER DEBRIS. PROTECT EXISTING VEGETATION AS FLAGGED BY ENGINEER. SEE CONTRACT PROVISIONS.
- INSTALL 8-INCH STRAW WATTLES AT APPROXIMATELY 3-FT. INTERVALS ON SLOPE FOLLOWING CONTOURS, AS DIRECTED BY ENGINEER. SEE CONTRACT PROVISIONS AND DETAILS.
- COMPOST BLANKET, 3-INCH SETTLED DEPTH.
  PNEUMATIC OR CONVEYER APPLICATION
  ONLY. SEE SECTION 8-01.3(4) OF THE
  STANDARD SPECIFICATIONS AND CONTRACT
  PROVISIONS
- 4 SEEDING, FERTILIZING AND MULCHING. SEE SECTION 8-02.3(9) OF THE CONTRACT PROVISIONS.
- BIODEGRADABLE EROSION CONTROL BLANKET.
  ANCHOR ABOVE UPPER EDGE OF SLOPE. SEE
  CONTRACT PROVISIONS AND DETAILS.
- SITE AND SURFACE PREPARATION FOR RESTORATION PLANTING. REMOVE LOOSE ROCKS, ROOTS, AND OTHER DEBRIS FROM DISTURBED AREAS AS STAKED BY ENGINEER. LOOSEN ANY COMPACTED SOIL WITH HAND TOOLS. PRUNE BROKEN STEMS AND BRANCHES.
- BARK MULCH, 3-INCH SETTLED DEPTH. APPLY TO DISTURBED AREAS AS STAKED BY ENGINEER, AFTER SURFACE PREPARATION FOR RESTORATION (NOTE 6). SEE CONTRACT PROVISIONS



COMPOST, SEEDING AND EROSION CONTROL BLANKET PLACEMENT

1

FILE NAME	C:\Users\piercea\OneDrive - Washington State Department of Transportation\Desktop\p	se sheet.dgi	1						CD 44	Plot 2
TIME	1:08:29 PM			REGION STATE	FED.AID PROJ.NO.	OF WASA			SR 14	PLAN REF NO
DATE	3/14/2023			10 WASH	NHPP-0014(088)	THE WILLS			1 MILE W OF SALMON FALLS RD	NA2
PLOTTED BY	PierceA			IU WASH	'''''		_		REPAIR DEBRIS FENCE	1472
DESIGNED BY	B KNAPP			JOB NUMBER		A CLAMATIC III A THAT		Washington State	REFAIR DEBRIS FENCE	SHEET
ENTERED BY	B KNAPP			23X337					RE-ADVERTISEMENT	1 13
CHECKED BY	D CORLETT			CONTRACT NO.	LOCATION NO.	APE ARCHI		Department of Transportation	·	OF 0
PROJ. ENGR.	M. BRIGGS				XL 6376	SEE SHEET CT1 DATE	DATE	- <b> </b>	SOIL PREPARATION	ZZ SHEETS
REGIONAL ADM.	. C. FRANCIS REVISION	DATE	BY		1 72 3370	P.E. STAMP BOX	P.E. STAMP BOX		l	SHEETS



#### CONSTRUCTION NOTES


SURFACE PREPARATION PRIOR TO COMPOST BLANKET PLACEMENT. SMOOTH SLOPE SURFACE AS DIRECTED BY ENGINEER. REMOVE ALL LOOSE ROCKS, ROOTS, VEGETATION AND OTHER DEBRIS. PROTECT EXISTING VEGETATION AS FLAGGED BY ENGINEER. SEE CONTRACT PROVISIONS.

NOT TO SCALE

- INSTALL 8-INCH STRAW WATTLES AT APPROXIMATELY 3-FT. INTERVALS ON SLOPE FOLLOWING CONTOURS, AS DIRECTED BY ENGINEER. SEE CONTRACT PROVISIONS AND DETAILS
- COMPOST BLANKET, 3-INCH SETTLED DEPTH.
  PNEUMATIC OR CONVEYER APPLICATION
  ONLY. SEE SECTION 8-01.3(4) OF THE
  STANDARD SPECIFICATIONS AND CONTRACT
  PROVISIONS
- SEEDING, FERTILIZING AND MULCHING. SEE SECTION 8-02.3(9) OF THE CONTRACT PROVISIONS
- BIODEGRADABLE EROSION CONTROL BLANKET.
  ANCHOR ABOVE UPPER EDGE OF SLOPE. SEE
  CONTRACT PROVISIONS AND DETAILS.
- SITE AND SURFACE PREPARATION FOR RESTORATION PLANTING. REMOVE LOOSE ROCKS, ROOTS, AND OTHER DEBRIG FROM DISTURBED AREAS AS STAKED BY ENGINEER. LOOSEN ANY COMPACTED SOIL WITH HAND TOOLS. PRUNE BROKEN STEMS AND BRANCHES.
- BARK MULCH, 3-INCH SETTLED DEPTH. APPLY TO DISTURBED AREAS AS STAKED BY ENGINEER, AFTER SURFACE PREFARATION FOR RESTORATION (NOTE 6). SEE CONTRACT PROVISIONS.

#### NOTES

- 1. INSTALL STRAW WATTLES ON PREPARED SLOPE SURFACE.
- 2. INSTALL WATTLES PERPENDICULAR TO FLOW ALONG CONTOURS.
- 3. DRIVE PRE-BENT REBAR STAKES THROUGH STRAW WATTLES INTO SOIL SLOPE AT 24-INCH INTERVALS. REBAR SHALL BE INSTALLED PERPENDICULAR TO THE SLOPE AT A MINIMUM 2 FOOT DEPTH. SIX INCH BENT END OF STAKE SHALL BE DRIVEN INTO WATTLE.
- 4. WATTLES SHALL BE FLUSH TO THE GROUND SURFACE WITH NO GAPS OR BENDS. WATTLES SHALL NOT BE COMPRESSED TO A DIAMETER OF LESS THAN 6 INCHES DURING STAKING. DO NOT TRENCH WATTLES.
- 2. OVERLAP ADJACENT WATTLE ENDS 12" BEHIND ONE ANOTHER AND STAKE IN PLACE.



FILE NAME	G:\Roadside\01_ projects\014\	11 Columbia R. Gorge Nat. Scenia Area\MP 25 vic Debi	ris Flow Fen	ce 20	21\CAD\MT	0666	SR14 Debris Fence Roadside	PS 2.dgn			
TIME	2:45:11 PM				REGION ST	TATE	FED.AID PROJ.NO.	OF WASHIA			ı
DATE	3/9/2023				10 W/	ASH	NHPP-0014(088)	Transfer of the state of the st			ı
PLOTTED BY	knappb				10 10	4311			_		ı
DESIGNED BY	B KNAPP				JOB NUMBE		//	Attle Diller		Washington State	ı
ENTERED BY	B KNAPP				23X33	7	<u> </u>	Jamy Fill Could	<b>\</b>		ı
CHECKED BY	D CORLETT				CONTRACT	NO.	LOCATION NO.	SCAPE ARCHI		Department of Transportation	
PROJ. ENGR.	M. BRIGGS						XL 6376	SEE SHEET CT1	DATE		ı
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY			AE 3370	P.E. STAMP BOX	P.E. STAMP BOX		ı

SR 14
1 MILE W OF SALMON FALLS RD
REPAIR DEBRIS FENCE
RE-ADVERTISEMENT
SOIL PREPARATION


Plot 1

PLAN REF N

NA3

14

22 SHEETS



#### ROADSIDE RESTORATION PLANT MATERIAL SCHEDULE

Symbol	Plant Code	Botanical Name	Common Name	Height	Root Type	A.S.N.S.	Spacing	Layout	Notes	Total in mix *
N/A	TREES (TMR)	Pseudotsuga menziesii	Douglas Fir	#7 min. (3' min.)	Cont.	4.7.2 Type 4	where staked	na	Min. 24" spread. Unsheared. Do not stake.	10
1477	TREED (THIR)									
		Amelancher alnifolia	Western Serviceberry	18"-36"	B.R.	3.4.2 Type 3	where staked	na	4 canes min.	50
		Holodiscus discolor	Creambush Oceanspray	18"-36"	B.R.	3.4.2 Type 3	where staked	na	4 canes min.	50
	SHRUB Mix A (SMA)	Mahonia aquifolium	Tall Oregon Grape	#1	Cont.	5.7.2 Type 4	where staked	na	3 stems min.	100
	CIMOD IIIX / (CIMI)	Polystichum munitum	Sword Fern	#1	Cont.		where staked	na	5 fronds min.	100
		Symphoricarpos albus	Snowberry	18"-36"	B.R.	3.3.2 Type 2	where staked	na	4 canes min.	250
		Elymus glaucus	Blue Wild Rye		10 ci Plug or B.R.		12" oc	Triang.	5" min. root length/ 4" min top growth	600
	GRASS MIX A (GMA)	Festuca idahoensis	Idaho Fescue		10 ci Plug or B.R.		12" 00	Triang.	5" min. root length/ 4" min top growth	450
	GRASS MIX A (GMA)	Symphoricarpos albus	Snowberry	6"-12"	10 ci Plug or B.R.		24" oc	Triang.	5" min. root length/ 6" min top growth	350
		Achillea millefolium	Yarrow		10 ci Plug or B.R.		12" 00	Triang.	5" min. root length	100
		Anaphalis margaritacea	Pearly Everlasting		10 ci Plug or B.R.		12" oc	Triang.	5" min. root length	100
	GRASS MIX B (GMB)	Elymus glaucus	Blue Wild Rye		10 ci Plug or B.R.		12" 00	Triang.	5" min. root length/ 4" min top growth	750
		Festuca idahoensis	Idaho Fescue		10 ci Plug or B.R.		12" 00	Triang.	5" min. root length/ 4" min top growth	550
		Koeleria macrantha	Prairie Junegrass		10 ci Plug or B.R.		12" oc	Triang.	5" min. root length/ 4" min top growth	100

Balled and Burlaped B.R. Cont. O.C. Bare Root Container

On Center A.S.N.S. American Standards for Nursery Stock


\*APPROXIMATE QUANTITIES, CONTRACTOR SHALL VERIFY QUANTITIES IN THE FIELD


#### PLANTING NOTES:

- 1. All material shall meet the requirements of the American Standard Nursery Stock, April 14, 2014. Conflicts between the ASNS and these specifications, then these specifications shall apply. A letter of compliance with the "American Standard of Nursery Stock" is required from the supplier for all plant material.
- 2. All plant material shall be nursery grown stock. Container plant material shall be well rooted in pot and meet requirements of Section 9-14.7(1) and 9-14.7(2) of the contract provisions.
- 3. Tree heights shall be measured at the midpoint between the uppermost whorl and the tip of the leader.
- 4. Planting areas shall be staked by contractor and approved by the Engineer prior to planting.
- 5. No plant material shall be planted until it has been inspected and approved for planting by the Engineer.
- 6. Plant material shall be stored and handled per section 9-14.7(3) of the contract provisions.

- 8. Plants to be randomly mixed within designated plant groups as approved by the Engineer unless specified otherwise. Completely remove burlap, wire baskets, plastic, string or wire lacing fromthe plant material and planting hole. Roots of bareroot stock shall not be bunched, curled, twisted, or unreasonably bent when placed in the planting hole. Loosen sides and roots of container plants prior to installation, cut circling roots. All plant crowns to be free
- 9. See planting details and contract provisions.


FILE NAME	G:\Roadside\01_ projects\014\	11 Columbia R. Gorge Nat. Scenia Area\MP 25 vic Debr	ris Flow Fen	ce 2021\CAD\MT066	SR14 Debris Fence Roadside	PS 2.dgn			OD 44	Plot 1
TIME	2:47:22 PM			REGION STATE	FED.AID PROJ.NO.	OF WAS			SR 14	PLAN REF NO
DATE	3/9/2023			10 WASH	NHPP-0014(088)	A STEEL ROOM OF THE STEEL STEE			1 MILE W OF SALMON FALLS RD	NB1
PLOTTED BY	knappb			IU WASI	, , , , , , , , , , , , , , , , , , , ,		<u> </u> -		DEDAID DEDDIG FENCE	
DESIGNED BY	B. KNAPP			JOB NUMBER		LIMMEN IN A TITLE		Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	B. KNAPP			23X337	·				RE-ADVERTISEMENT	16
CHECKED BY	D. CORLETT			CONTRACT NO.	LOCATION NO.	EXP.1012234		Department of Transportation	TE ABTERNIOUNER	OF
PROJ. ENGR.	M. BRIGGS				XL 6376	SEE SHEET CT1	DATE		PLANTING PLAN	22 SHEETS
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY	XL 0370	P.E. STAMP BOX	P.E. STAMP BOX			SHEETS






CONCEPT ILLUSTRATION. ACTUAL AREAS TO BE DETERMINED AS DIRECTED BY ENGINEER.

FILE NAME	G:\Roadside\01_ projects\014\	11 Columbia R. Gorge Nat. Scenia Area\MP 25 vic Debi	ris Flow Fer	nce 20	21\CAD\MT0666	SR14 Debris Fence Roadside	PS 2.dgn			<b>an</b> 44	Plot 1
TIME	3:07:08 PM				REGION STATE	FED.AID PROJ.NO.	OF WASH			SR 14	PLAN REF NO
DATE	3/14/2023				10 WASH	NHPP-0014(088)	E PHE CONTO			1 MILE W OF SALMON FALLS RD	NB3
PLOTTED BY	knappb				IU WASH		500 000 000				1403
DESIGNED BY	B. KNAPP				JOB NUMBER		1 1 2 1 7 1	_	Washington State	REPAIR DEBRIS FENCE	SHEET
ENTERED BY	B. KNAPP				23X337		N Samul & Comin		9	RE-ADVERTISEMENT	18
CHECKED BY	D. CORLETT				CONTRACT NO.	LOCATION NO.	SC EXP.10 PCHIT	•	Department of Transportation	RE ADVERTIGEMENT	OF
PROJ. ENGR.	M. BRIGGS					XL 6376	SEE SHEET CT1	DATE		PLANTING PLAN	SHEETS
REGIONAL ADM	C FRANCIS	REVISION	DATE	RY	1	XL 03/0	DE STAMP BOY	DE STAMP BOY			SHEETS






(2)

TREE PLANTING

NOT TO SCALE

FILE NAME	G:\Roadside\01_ projects\014	111 Columbia R. Gorge Nat. Scenia Area\MP 25 vic Debi	ris Flow Fen	nce 20	21\CAD\MT066	SR14 Debris Fence Roadside	PS 2.dgn			SR 14	Plot 1
TIME	2:54:25 PM				REGION STATE NO.	FED.AID PROJ.NO.	OF WASHIN			1 MILE W OF SALMON FALLS RD	PLAN REF NO
DATE	3/9/2023				10 WASH	NHPP-0014(088)	PAME CONTROL CONTROL			I WILE W OF SALWON FALLS RD	NR4
PLOTTED BY	knappb				10 WASI	,	600			REPAIR DEBRIS FENCE	1104
DESIGNED BY	B. KNAPP				JOB NUMBER		111 Different ( )		Washington State		SHEET
ENTERED BY	B. KNAPP				23X337		1 Example Stell County		,	RE-ADVERTISEMENT	19
CHECKED BY	D. CORLETT				CONTRACT NO.	LOCATION NO.	10 C EXP 10 12 HIT		Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS				1	XL 6376	SEE SHEET CT1	DATE	_	PLANTING PLAN	22 SHEETS
REGIONAL ADM.	. C. FRANCIS	REVISION	DATE	BY	1	XL 0370	P.E. STAMP BOX	P.E. STAMP BOX		1	SHEETS



1) 2 REQUIRED

G20-2A

END
ROAD WORK

AHEAD

48"

W20-1

AHEAD

W20-1

AHEAD

48" X 24"

FOR PROJECT
INFORMATION
1-866-279-0730

Washington State
W20-1

AHEAD

W20-1

CLASS A SIGN SCHEDULE

25.80

25.16

25.16

SIGN

W20-1

G20-2A

G24-501

SR-14

WB (MP) EB (MP)

G24-501

24.65

25.73

25.73

PCMS

BEFORE PROJECT START

1 2

SR 14 BEGINS
ROAD
WORK

2 SEC. 2 SEC.

LOCATE AT SR 14 MP 24.11 FOR EASTBOUND TRAFFIC, SR 14 MP 25.94 FOR WESTBOUND TRAFFIC. INSTALL FIVE CALENDAR DAYS PRIOR TO START DATE.

**PCMS** 

#### DURING PROJECT ACTIVITIES


1	2	
ROAD WORK AHEAD	EXPECT DELAYS	
2 SEC	2 SEC	

LOCATE AT SR 14 MP 24.11 FOR EASTBOUND TRAFFIC, SR 14 MP 25.94 FOR WESTBOUND TRAFFIC.

#### **NOTES**

- 1. CLASS A SIGNS SHALL BE POST MOUNTED.
- 2. ALL SIGNS ARE BLACK ON ORANGE UNLESS OTHERWISE SPECIFIED.
- 3. PRELIMINARY SIGN LOCATIONS TO BE STAKED BY THE ENGINEER. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING SIGN LOCATION DOES NOT CONFLICT WITH ANY EXISTING UNDERGROUND UTILITIES. IF CONFLICT IS ENCOUNTERED CONTRACTOR SHALL ADJUST SIGN LOCATION TO AVOID CONFLICT.

FILE NAME	G:\444302\03 - Design\D01421I	D SR14 1 Mile W	of Salmon Fa	alls Rd - Re	pair Debris	Fence\20-CAD	DD-Pla	ns\20-1	1 PS&E	Sheets\XL6376_PS_TC.dgn
TIME	11:05:46 AM							REGION NO.	STATE	FED.AID PROJ.NO.
DATE	2/28/2023							10	WASH	NHPP-0014(088)
PLOTTED BY	PierceA							10	WASH	
DESIGNED BY	A. PIERCE								IUMBER	
ENTERED BY	A. PIERCE							23X	337	
CHECKED BY	K. LEI							CONTR	RACT NO.	LOCATION NO.
PROJ. ENGR.	M. BRIGGS									XL 6376
REGIONAL ADM.	C. FRANCIS		REVISION	l		DATE	BY			XE 03/0



SR 14 1 MILE W OF SALMON FALLS RD REPAIR DEBRIS FENCE RE-ADVERTISEMENT


CLASS A SIGN PLAN

SHEET
20
OF
22
SHEETS

Plot 4

LAN REF NO

CS1




	MININ	IUM S	HOUL	DER T	APER	LENG	TH =	L/3 (fe	et)	
SHOULDER				Pos	ted Sp	eed (n	nph)			
WIDTH (feet)	25	30	35	40	45	50	55	60	65	70
8'		1	-	-	120	130	150	160	170	190
10'	-	-	-	-	150	170	190	200	220	240

SIGN SPACIN	NG = X (1)	
FREEWAYS & EXPRESSWAYS	55 / 70 MPH	1500' ±
RURAL HIGHWAYS	60 / 65 MPH	800' ±
RURAL ROADS	45 / 55 MPH	500' ±
(1) ALL SPACING MAY BE ADJUSTED RAMPS, AT-GRADE INTERSECTIONS		INTERCHANGE

CHANNELIZATION DEVICE SPACING (feet)								
MPH	TAPER	TANGENT						
50/70	40	80						
35/45	30	60						
35/45	30	60						

BUFFER DATA										
LONGITUDINAL BUFFER SPACE = B										
SPEED (MPH)	25	30	35	40	45	50	55	60	65	70
LENGTH (feet)	155	200	250	305	360	425	495	570	645	730
TRANSPORTABLE ATTENUATOR ROLL ALIEAR DISTANCE - R										

TRANSPORTABLE ATTENUATOR ROLL AHEAD DISTANCE = R								
	VEHICLE WEIG 0 TO 22,000 lbs		HOST VEHICLE WEIGHT > 22,000 lbs.					
< 45 MPH	45-55 MPH	> 55 MPH	< 45 MPH	45-55 MPH	> 55 MPH			
100'	123'	172'	74'	100'	150'			



- TEMPORARY SIGN LOCATION
- TRAFFIC SAFETY DRUM

#### TRANSPORTABLE ATTENUATOR

### SHOULDER CLOSURE - HIGH SPEED

#### NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01421I	D SR14 1 Mile W of Salmon Falls Rd - Repair Debris	Fence\20-CA	DD-Pla	ans\20-1	1 PS&E	Sheets\XL6376_PS_TC.dgn			
TIME	1:01:12 PM				REGION	STATE	FED.AID PROJ.NO.	1		
DATE	2/2/2023				10	WASH	NHPP-0014(088)			
PLOTTED BY	piercea				10	WASH				
DESIGNED BY	A. PIERCE				JOB N	-				Washington
ENTERED BY	A. PIERCE				23X	337				Washington
CHECKED BY	K. LEI				CONTR	ACT NO.	LOCATION NO.			Department of Tra
PROJ. ENGR.	M. BRIGGS						XL 6376	— DATE	DATE	
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY			XE 0310	P.E. STAMP BOX	P.E. STAMP BOX	

on State Transportation

NOTES

20' (FT) O.C.

SR 14 1 MILE W OF SALMON FALLS RD REPAIR DEBRIS FENCE RE-ADVERTISEMENT

TRAFFIC CONTROL PLAN

1. NO ENCROACHMENT IN TRAVELED LANE. IF ENCROACHMENT IS

2. DEVICE SPACING FOR THE DOWNSTREAM TAPER SHALL BE

NECESSARY, LANE SHALL BE CLOSED.

3. ALL SIGNS ARE BLACK ON ORANGE.

PLAN REF NO TC2 SHEET

22

OF

22

SHEETS

Plot 6