# **INDEX**

# INDEX (CONTINUED)

SHEET NO.	PLAN REFERENCE NO.	TITLE
		VOLUME 1
1	IN1	INDEX
2	VM1	VICINITY MAP
3 - 4	SQ1 - SQ2	SUMMARY OF QUANTITIES
		VOLUME 2
5	IN1	INDEX
6	CT1	CERTIFICATION SHEET
7	RS1	ROADWAY SECTIONS
8 - 11	SU1 - SU4	STAGING PLANS
12	QT1	QUANTITY TABULATION
13	EC1	SITE PREP AND TESC PLANS
14	IL1	TEMPORARY ILLUMINATION PLAN
15	SG1	SIGNAL SYSTEM MODIFICATION
16 - 37	B1 - B22	BRIDGE PLANS
38	QT2	QUANTITY TABULATION
39	MK1	GUARDRAIL AND PAVEMENT MARKING
40	SN1	CONSTRUCTION SIGNING CLASS A
41 - 47	TC1 - TC7	TRAFFIC CONTROL PLANS
48	DU1	DETOUR PLAN

SHEET NO.	PLAN REFERENCE NO.	TITLE

Plot 24

IN1

PLAN
REFERENCE
NO.
SHEET
OF
SHEETS

NOTE: ALL SHEET REFERENCES, FIRST NOS. OF STRUCTURE CODE DESIGNATIONS AND MATCH LINE SHEET REFERENCES, ETC., THROUGHOUT THE PLANS, REFER TO THE ENTRY IN THE PLAN REFERENCE NUMBER BOX.

FILE NAME	G:\444302\03 - Design\D014220	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD	-Plans\20-2 F	PS&E	Sheets\D01422	G_PS_INVM_INDEX AND VICIN	TY MAP.dgn			
TIME	10:21:51 AM				REGION STATE	FED.AID PROJ.NO.				SR 14
DATE	6/15/2023			1 1	40 14/4 61	ER-STBG-2C05001				
PLOTTED BY	GregorR				10 WASE	] =::: 0:: 20 = 00000:				LIESER ROAD BRIDGE
DESIGNED BY	R. GREGORIO				JOB NUMBER				Washington State	EMERGENCY BRIDGE REPAIR
ENTERED BY	CGAEO				22X347				ı	
CHECKED BY	T. HARTMANN			1 1	CONTRACT NO.	LOCATION NO.			Department of Transportation	
PROJ. ENGR.	M. BRIGGS					XL6636	— DATE	DATE		INDEX
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		1 725050	P.E. STAMP BOX	P.E. STAMP BOX		

# PROJECT LICENSED PROFESSIONAL CERTIFICATES

amy C. Leland LisaRene Schilperoort Amy C Leland Richard Zeldenrust Jul 26, 2023 Jul 26, 2023 Jul 26, 2023 Jul 26, 2023 AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION. SUPERVISION. SUPERVISION. AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION. SUPERVISION. SUPERVISION. SUPERVISION. AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY AS A LICENSED PROFESSIONAL IN DIRECT RESPONSIBLE CHARGE OF DEVELOPING THIS CONTRACT, I CERTIFY THAT ALL PLANS THAT CONTAIN MY STAMP HAVE BEEN DEVELOPED UNDER MY SUPERVISION. SUPERVISION. SUPERVISION. SUPERVISION.

#### NOTES

THIS PLAN SET WAS DEVELOPED ELECTRONICALLY UNDER THE DIRECT SUPERVISION OF THE LICENSED PROFESSIONALS THAT HAVE AFFIXED THEIR SIGNATURE TO THIS PAGE.

THIS SHEET SERVES AS THE CERTIFICATION BY THE ABOVE LICENSED PROFESSIONALS OF ALL SHEETS IN THIS PLAN SET WHERE THEIR STAMPS AND SIGNATURES APPEAR.

FILE NAME	G:\444302\03 - Design\D014220	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD	-Plans\20-2 P	S&E	Sheets\[	D014220	PS_INVM_INDEX AND VICIN	TY MAP.dgn
TIME	10:37:50 AM				REGION NO.	STATE	FED.AID PROJ.NO.	
DATE	6/15/2023				10	WASH	ER-STBG-2C05001	
PLOTTED BY	GregorR				10	WASH		
DESIGNED BY	R. GREGORIO				JOB NU			
ENTERED BY	CGAEO				22X	347		
CHECKED BY	T. HARTMANN				CONTRA	ACT NO.	LOCATION NO.	
PROJ. ENGR.	M. BRIGGS						XL6636	DATE
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY			7120000	P.E. STAMP BOX

Washington State
Department of Transportation


DATE

SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR

**CERTIFICATION SHEET** 

PLAN REF NO CT1

SHEET
6
0F
48
SHEETS




### NOTES:

- 1. ALL DEPTHS SHOWN ARE COMPACTED DEPTHS.
- 2. ROADWAY REMOVAL LIMIT VARIES FROM 8.04'TO 9.21'.

#### CONSTRUCTION NOTES:

- 1 COMMERCIAL HMA CL. 3/8 IN. PG 58H-22
- 2 CRUSHED SURFACING BASE COURSE
- 3 BRIDGE CONCRETE DECK



FILE NAME	G:\444302\03 - Design\D014220	G SR 14 Lieser Rd Br - Emergency	Br Repair\20-CADD-Plans\20-2	PS&E	Sheets\	D01422G	PS_RS_ROADWAY SECTION	4
TIME	5:11:25 PM				REGION	STATE	FED.AID PROJ.NO.	7
DATE	6/15/2023				10	WASH	ER-STBG-2C05001	
PLOTTED BY	GregorR				יי ן	WASH		1/
DESIGNED BY	R. GREGORIO				JOB N			1/
ENTERED BY	CGAEO				22X	347		ľ
CHECKED BY	T. HARTMANN				CONTR	ACT NO.	LOCATION NO.	1
PROJ. ENGR.	M. BRIGGS				1		XL6636	ı
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY			AL0030	$\perp$



<b>7</b>
Washington State Department of Transportation

	Plot 1
SR 14	PLAN REF NO
LIESER ROAD BRIDGE	RS1
EMERGENCY BRIDGE REPAIR	SHEET 7 OF
ROADWAY SECTIONS	48 SHEETS

#### STAGING GENERAL NOTES


- 1. SEE SPECIAL PROVISIONS FOR CLOSURES AND LANE RESTRICTIONS.
- 2. CONTRACTOR SHALL COORDINATE WITH WSDOT SIGNALS BEFORE EACH AND EVERY STAGE TO ENSURE PROPER CONFIGURATION OF SIGNAL DETECTION (STAGES 0, 1B, 1C, 2, AND 3).
- 3. THE CONTRACTOR SHALL REMOVE CONFLICTING PAVEMENT MARKINGS.
- 4. EMERGENCY SERVICES SHALL BE ACCOMMODATED THROUGH THE WORK ZONE WITH AS SHORT OF A DELAY AS POSSIBLE.

#### STAGE 0: PRIOR TO BRIDGE WORK

- 1. INSTALL TESC MEASURES. SET CLASS A SIGNS. INSTALL WAVETRONIX
- FOR TEMPORARY DETECTION INSTALL TEMPORARY ILLUMINATION.
- 2. SEE SHEET EC1, CT1, SG1 AND IL1.


### STAGE 1A: REPLACE GIRDER G

- 1. SET TEMPORARY BARRIER.
- 2. SEE SHEET SU2 FOR STAGE 1A PLAN.
- 3. SEE SHEET B3 FOR SAWCUT LIMITS.
- 4. SEE GIRDER REPLACEMENT SEQUENCE ON SHEET B7.




#### STAGE 1B: CLOSURE POUR/CURE (14 DAYS)

- 1. TEMPORARY BARRIER TO REMAIN IN PLACE FROM STAGE 1A.
- 2. REDUCE TO SINGLE LANE (NB ONLY).
- 3. SEE SHEET SU3 FOR STAGE 1B PLAN.
- 4. SEE SHEET DU1 FOR DETOUR SIGNS.




#### STAGE 1C: CONSTRUCT PERMANENT BRIDGE BARRIER

- 1. RETURN TO STAGE 1A CONFIGURATION. TEMPORARY BARRIER TO REMAIN IN PLACE. 2. SEE SHEET SU2 FOR STAGE 1C PLAN.




## STAGE 2: GIRDER A REPAIR AND CURE (5 DAYS)

- 1. REMOVE TEMPORARY BARRIER FROM STAGE 1.
- 2. REDUCE TO SINGLE LANE (NB ONLY).
- 3 SEE SHEET SU4 FOR STAGE 2 PLAN.
- 4. SEE SHEET B21 FOR GIRDER REPAIR DETAILS.
- 5. SEE SHEET DU1 FOR DETOUR SIGNS.



#### STAGE 3: COMPLETE B THROUGH F BEAM REPAIRS AND GUARDRAIL REPLACEMENT.

- 1. SEE SHEET B21 FOR GIRDER REPAIR DETAILS. SEE SHEET MK1 FOR GUARDRAIL SCHEDULE. UTILIZE FLAGGER OPERATION ON SHEET TC7 FOR GUARDRAIL REPLACEMENT WORK.
- 2. REMOVE CHANNELING DEVICES AND TEMPORARY PAVEMENT MARKING.
- 3. INSTALL PAINT LINE, PLASTIC CROSSWALK LINE, AND PLASTIC STOP LINE. SEE SHEET MK1 FOR PAVEMENT MARKING
- 4. CONFIGURE TRAFFIC SIGNAL DETECTION FOR PERMANENT INSTALL. SEE SHEET SG1 SIGNAL SYSTEM MODIFICATION.




LEGEND:

PEDESTRIAN ACCESS ROUTE

FILE NAME	G:\444302\03 - Design\D014220	G SR 14 Lieser Rd Br	- Emergency	Br Repair\20-CADD	-Plans\20-2	PS&E	Sheets\	D014220	PS_SU_STAGING_PLANS.	lgn
TIME	4:39:22 PM						REGION NO.	STATE	FED.AID PROJ.NO.	П
DATE	6/15/2023							WASH	ER-STBG-2C0500	1
PLOTTED BY	GregorR						יי ן	WASH		- L
DESIGNED BY	R. GREGORIO							IUMBER		- 12
ENTERED BY	CGAEO						22X	347		- 1 "
CHECKED BY	T. HARTMANN						CONTR	RACT NO.	LOCATION NO.	
PROJ. ENGR.	M. BRIGGS						1		XL6636	
REGIONAL ADM.	C. FRANCIS		REVISION		DATE	BY			AL3030	






Washington State Department of Transportation	
	ı

SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR

SU1 48 STAGING PLANS

Plot 1 PLAN REF NO



#### CONSTRUCTION NOTES:

- TEMPORARY PAVEMENT MARKING DOUBLE CENTERLINE (YELLOW)
- TEMPORARY PAVEMENT MARKING DOTTED EXTENSION LINE (YELLOW) **(2)**
- TEMPORARY PAVEMENT MARKING STOP LINE (24")

#### NOTES

- 1. TEMPORARY SIGNAL DETECTION NEEDS TO BE MODIFIED BEFORE OPENING TO TRAFFIC.
- 2. EXTEND CHANNELING DEVICES ONTO RAMP AND TAPER ACROSS SHOULDER.
- 3. CHANNELING DEVICE SPACING RECOMMENDED AT 20'C/C ON TANGENTS AND 10'C/C ON RADIUS.


PCMS								
1	2							
LIESER BRIDGE WORK	NARROW ROADWAY AHEAD							
2 SEC	2 SEC							

#### LEGEND:

- TEMPORARY SIGN LOCATION
- TEMPORARY SIGN LOCATION (5'MIN HEIGHT)
- TRAFFIC SAFETY DRUM
- TEMPORARY BARRIER
- TUBULAR MARKER

PCMS PORTABLE CHANGEABLE MESSAGE SIGN

DIRECTION OF TRAVEL



# LIESER ROAD BRIDGE - STAGE 1A AND 1C

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D014220	G SR 14 Lieser Rd Br - Emergency	Br Repair\20-CADD-Plans\20-2	PS&E	Sheets\	D014220	S_PS_SU_STAGING_PLANS.dgn
TIME	4:41:57 PM				REGION	STATE	FED.AID PROJ.NO.
DATE	6/15/2023				10	WASH	ER-STBG-2C05001
PLOTTED BY	GregorR				יי ן	WASH	
DESIGNED BY	R. GREGORIO					IUMBER	
ENTERED BY	CGAEO				22X	347	
CHECKED BY	T. HARTMANN				CONTR	RACT NO.	LOCATION NO.
PROJ. ENGR.	M. BRIGGS				]		XL6636
DECIONAL ADM	C EDANCIS	DEVISION	DATE	DV	1	- 1	ALCOJO






265 LF

	SR	14			
LIESER	ROA	۸D	BRI	IDGE	
EMERGENC	Y B	RID	GE	REPAIR	

STAGING PLANS

SU2 48 SHEETS



#### **CONSTRUCTION NOTES:**

- 1 TEMPORARY PAVEMENT MARKING DOUBLE CENTERLINE (YELLOW)
- (2) TEMPORARY PAVEMENT MARKING DOTTED EXTENSION LINE (YELLOW)
- 3 TEMPORARY PAVEMENT MARKING STOP LINE (24")

#### NOTES:


- 1. TEMPORARY SIGNAL DETECTION NEEDS TO BE MODIFIED BEFORE OPENING TO TRAFFIC.
- 2. EXTEND CHANNELING DEVICE ONTO RAMP AND TAPER ACROSS SHOULDER.
- 3. CHANNELING DEVICE SPACING RECOMMENDED AT 20  $^{\circ}$  C/C ON TANGENTS AND 10  $^{\circ}$  C/C ON RADIUS.
- 4. DO NOT COVER R3-7R SIGN LOCATED ON SB LIESER RD. SEE SHEET SN1 FOR SIGN COVERING SCHEDULE.
- 5. INSTALL STOP LINE AT MINIMUM 50'FROM SIGNAL HEAD.
- 6. SEE SHEET SN1 FOR SIGN COVERING SCHEDULE.
- 7. DETOUR SIGNS SHALL BE IN PLACE BEFORE OPENING TO TRAFFIC. SEE SHEET DU1 FOR DETOUR SIGNS.

#### LEGEND:


- TEMPORARY SIGN LOCATION
- TEMPORARY SIGN LOCATION (5'MIN HEIGHT)
- TEMPORARY BARRIER
- TUBULAR MARKER

PCMS PORTABLE CHANGEABLE MESSAGE SIGN

DIRECTION OF TRAVEL



PCN	IS 2
1	2
LIESER AT SR 14 CLOSED	FOLLOW DETOUR ROUTE
2 SEC	2 SEC



# LIESER ROAD BRIDGE - STAGE 1B (ONE-WAY NB ONLY)

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422	G SR 14 Lieser R	d Br - Emergency	Br Repair\20-CADD	-Plans\20-2	PS&E	Sheets\	D014220	PS_SU_STAGING_PLANS.dgn	ī
TIME	4:48:31 PM						REGION	STATE	FED.AID PROJ.NO.	ı
DATE	6/15/2023						10	WASH	ER-STBG-2C05001	ı
PLOTTED BY	GregorR						יי ן	WASH		1
DESIGNED BY	R. GREGORIO							IUMBER		1
ENTERED BY	CGAEO						22X	347		ľ
CHECKED BY	T. HARTMANN						CONTR	RACT NO.	LOCATION NO.	ı
PROJ. ENGR.	M. BRIGGS						1		XL6636	ı
REGIONAL ADM	C FRANCIS		REVISION		DATE	BY	1		AL0030	






SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR

STAGING PLANS

SU3

SHEET
10
OF
48
SHEETS



#### CONSTRUCTION NOTES:

- 1 TEMPORARY PAVEMENT MARKING DOUBLE CENTERLINE (YELLOW)
- 2 TEMPORARY PAVEMENT MARKING DOTTED EXTENSION LINE (YELLOW)
- 3 TEMPORARY PAVEMENT MARKING STOP LINE (24")

#### NOTES:

- 1. TEMPORARY SIGNAL DETECTION NEEDS TO BE MODIFIED BEFORE OPENING TO TRAFFIC.
- 2. EXTEND CHANNELING DEVICE ONTO RAMP AND TAPER ACROSS SHOULDER.
- 3. CHANNELING DEVICE SPACING RECOMMENDED AT 20  $^{\circ}$  C/C ON TANGENTS AND 10  $^{\circ}$  C/C ON RADIUS.
- 4. DO NOT COVER R3-7R SIGN LOCATED ON SB LIESER RD. SEE SHEET SN1 FOR SIGN COVERING SCHEDULE.
- 5. INSTALL STOP LINE AT MINIMUM 50'FROM SIGNAL HEAD.
- 6. SEE SHEET SN1 FOR SIGN COVERING SCHEDULE.
- 7. DETOUR SIGNS SHALL BE IN PLACE BEFORE OPENING TO TRAFFIC. SEE SHEET DU1 FOR DETOUR SIGNS.

#### LEGEND:


- TEMPORARY SIGN LOCATION
- TEMPORARY SIGN LOCATION (5'MIN HEIGHT)
- TEMPORARY BARRIER
- TUBULAR MARKER

PCMS PORTABLE CHANGEABLE MESSAGE SIGN

DIRECTION OF TRAVEL

PCN	IS 1
1	2
LIESER BRIDGE WORK	NARROW ROADWAY AHEAD
2 SEC	2 SEC

PCN	IS 2
1	2
LIESER AT SR 14 CLOSED	FOLLOW DETOUR ROUTE
2 SEC	2 SEC



# LIESER ROAD - STAGE 2 (ONE-WAY NB ONLY)

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422	G SR 14 Lieser Rd Br -	Emergency Br Repair\	20-CADD-Plans\20-2	PS&E	Sheets\	D014220	S_PS_SU_STAGING_PLANS.dgn	Г
TIME	4:50:26 PM					REGION NO.	STATE	FED.AID PROJ.NO.	
DATE	6/15/2023						WASH	ER-STBG-2C05001	
PLOTTED BY	GregorR					יי ן	WASH		1
DESIGNED BY	R. GREGORIO						IUMBER		1
ENTERED BY	CGAEO					22X	347		ľ
CHECKED BY	T. HARTMANN					CONTR	RACT NO.	LOCATION NO.	ı
PROJ. ENGR.	M. BRIGGS					]		XL6636	ĺ
REGIONAL ADM.	C. FRANCIS	RI	EVISION	DATE	BY	1		ALOUSU	ı






SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR


STAGING PLANS


SU4


SHEET
11
0F
48
SHEETS


	QUANTITY TABULATION - SITE PREP AND TESC PLANS																			
TO THE SHOWIN	ST NUMBER OF THE "CODE" BELOW REFERS SHEET NO. OR THE SHEET REFERENCE NO. IG THE CONSTRUCTION FEATURE COND NUMBER REFERS TO THE RUCTION FEATURE FOUND ON THAT SHEET.	REMOVING GUARDRAIL		REMOVING PAINT LINE - DOUBLE CENTERLINE	REMOVING PAINT LINE - EDGE LINE	REMOVING PAINT LINE - DOTTED EXTENSION LINE	REMOVING PAINT LINE - STOP LINE		REMOVING RAISED PAVEMENT MARKER		INLET PROTECTION		HIGH VISIBILITY FENCE				GENERAL NOTES			
CODE EC1-1	LOCATION ↓ / UNIT OF MEASURE → STA 7+00 (17' RT) TO STA 8+60 (17' RT)	LF 160		LF	LF	LF	LF		HUND		EA		LF				3	GENERAL NOTES		
EC1-2 EC1-3 EC1-4 EC1-5 EC1-6 EC1-7 EC1-8 EC1-9 EC1-10 EC1-11 EC1-12 EC1-13 EC1-14 EC1-15	STA 8+56 (0' RT) TO STA 11+40 (0' RT)  STA 7+00 (0' RT) TO STA 7+66 (0' RT)  STA 7+00 (12' RT) TO STA 11+40 (12' RT)  STA 7+00 (12' LT) TO STA 11+40 (12' LT)  STA 8+56 (12' LT) TO STA 11+40 (12' LT)  STA 7+66 (0' RT) TO STA 8+56 (0' RT)  STA 7+66 (12' LT) TO STA 8+56 (12' LT)  STA 11+39 (0' LT) TO STA 11+39 (12' LT)  STA 7+30 (60' RT)  STA 7+30 (60' RT)  STA 9+04 (13' RT)  STA 10+20 (13' RT)  STA 10+25 (13' LT)  NW QUADRANT  NE QUADRANT			284 70	440 70 284	90 90	12		0.1		1 1 1 1 1		460 550				1 1 1 1 1 2 2	1. See STD PLN I-40.20 FOR INLET PROTECTION  2. See STD PLN I-30.17 FOR HIGH VISIBILITY FENCE  3. See Sheet MK1 FOR GUARDRAIL SCHEDULE	CE	
Entered Checked Proj.Eng.	PROJECT TOTAL  R. GREGORIO CGAEO T. HARTMANN M. BRIGGS n C. FRANCIS	160		354	794	180 REGION NO.  10  JOB NI 22X CONTRA	347	FED. AID F			5		1,010	Vashingtor Departmen	n State t of Trans	portation		SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR  QUANTITY TABULATION		
neg Admi	DATE DATE		REVISION		BY	CONTR	TOT NO.											QUANTITI INDULATION	48 SHEETS	













STAGE 1

- 1. RE-SET TEMPORARY CONCRETE BARRIER.
- 2. INSTALL DEBRIS CONTAINMENT SYSTEM.
- 3. REMOVE RAIL AND RAIL POSTS FROM EXISTING CONCRETE BARRIER AND STORE FOR REPLACEMENT ON NEW CONCRETE BARRIER.
- 4. INSTALL SHORING AS REQUIRED BEYOND BACK OF PAVEMENT SEAT, PARALLEL WITH CENTERLINE ROADWAY. REMOVE HMA AND EXCAVATE BEHIND BACK OF PAVEMENT SEAT TO FULLY EXPOSE END DIAPHRAGM.



- 1. PLACE CONTRACTOR DESIGNED TEMPORARY BRACING AND REINFORCEMENT BEAM.
- 2. SAWCUT AT THE LOCATIONS AND TO THE DEPTHS SHOWN. LOCATION OF SAWCUT MAY BE ADJUSTED WITH THE APPROVAL OF THE ENGINEER. SAWCUT AND REMOVE HMA OVERLAY (3" TO 4" THICK) PRIOR TO PERFORMING 3/4" SAWCUT IN THE CONCRETE DECK.
- 3. REMOVE 3'-0" PORTION OF SLAB AND PAD SHOWN IN HATCHED AREA INCLUDING REMOVAL OF DIAPHRAGMS OVER THE FULL DEPTH. SAVE TRANSVERSE SLAB AND DIAPHRAGM REINFORCEMENT EXTENDING FROM EXISTING REMAINING STRUCTURE. CLEAN AND ROUGHEN SIDE FACES OF CONCRETE AGAINST WHICH NEW CONCRETE WILL BE PLACED. REFER TO THE SPECIAL PROVISIONS FOR DECK REMOVAL EQUIPMENT LIMITATIONS IN AREAS WHERE EXISTING STEEL IS TO BE SAVED.



# STAGE 3

- 1. REMOVE 2'-6" SECTION OF SLAB AT PIER 2. SAVE LONGITUDINAL AND TRANSVERSE SLAB REINFORCEMENT EXTENDING FROM EXISTING REMAINING STRUCTURE. SEE SHEET B3 FOR DETAILS, REFER TO THE SPECIAL PROVISIONS FOR DECK REMOVAL EQUIPMENT LIMITATIONS IN AREAS WHERE EXISTING STEEL IS TO BE SAVED.
- 2. REMOVE THE CONCRETE BARRIER BACK TO THE CLOSEST JOINT IN SPAN 2. SAVE STEEL REINFORCEMENT EXTENDING FROM EXISTING REMAINING SLAB.
- 3. REMOVE HINGE DIAPHRAGM AND SAVE THE TRANSVERSE REINFORCEMENT EXTENDING FROM EXISTING REMAINING HINGE AND HINGE BARS AS SHOWN ON SHEET B5.
- 4. REMOVE END DIAPHRAGM AT BACK OF PAVEMENT SEAT AND INTERMEDIATE DIAPHRAGM OR REMOVE WITH GIRDERS
- 5. REMOVE PIER 1 DIAPHRAGM OR REMOVE WITH GIRDERS. SAVE TRANSVERSE STEEL AS SHOWN ON SHEET B6.
- 6. REMOVE THE DAMAGED GIRDER, SLAB AND BARRIER.

# NOTES:

- 1. THE CONTRACTOR SHALL DESIGN AND SUBMIT A DEMOLITION PLAN WITH DEBRIS CONTAINMENT SYSTEM FOR APPROVAL BY THE ENGINEER. THE DEMOLITION PLAN SHALL INCLUDE TEMPORARY BRACING AND GIRDER STABILIZATION DETAILS.
- 2. IT IS ASSUMED THE CONTRACTOR WILL REMOVE THE CONCRETE BARRIER WITH THE OUTSIDE DAMAGED GIRDER. THE CONTRACTOR MAY ELECT TO REMOVE THE BARRIER PRIOR TO REMOVING THE GIRDERS. THE SEQUENCE SHALL BE INCLUDED IN THE DEMOLITION PLAN.
- THE TEMPORARY BRACING, FULL LENGTH REINFORCEMENT BEAM, AND DEBRIS CONTAINMENT SYSTEM SHOWN ARE SCHEMATIC AND ARE ONLY A SUGGESTION TO THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR STABILIZING THE EXISTING GIRDER AND CONTROLLING DEBRIS DURING REMOVAL.
- THE CONTRACTOR MAY RELOCATE THE TRANSVERSE SAWCUT IN THE HMA DEPENDING ON THE SHORING OR EXTRA EXCAVATION METHODS USED. WITH THE APPROVAL OF THE ENGINEER

- 1									
Ë	FILE PATH / NAME	pw://projectstore.wsdot	t.wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/	/2022_Emei	gency	2 <u>86670</u> h_	XL6626/_	D
뿛	BRIDGE DES. ENG.	LELAND, A							1
	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	ĺ
ĕ	SUPERVISOR	ZELDENRUST, R					JOB	NUMBER	ĺ
盎	DESIGNED BY	BONDY, T	09/22						l
	CHECKED BY	DORNSIFE, R	07/23						ĺ
	ENTERED BY	TUBBS, N	09/22				CONT	RACT NO.	ĺ
	PRELIM. PLAN BY								l
ß	ARCH. / SPEC.			REVISION	DATE	BY			L





PE STAMP BOX

THE THE PARTY OF T	LIESER EMERGENC

SR 14 ROAD BRIDGE CY BRIDGE REPAIR REMOVAL SEQUENCE


PLAN REF NO

B2


SHEET


48

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:07 PM PLOTTED BY: \$\$USERNAME\$\$




SHOWN NEAR PIER 2










# **SLAB & REINFORCEMENT REMOVAL NEAR PIER 2**

\*CUT TOP #9 & #10 ALONG LINE NORMAL TO & BRIDGE (TYP.) SAVE 2'-0" MIN. OF BOT. #5 LONGITUDINAL REINF. (TYP.)

ᇤ	FILE PATH / NAME	pw://projectstore.wsdot.v	va.gov:WSDOT/Documents	ts/_HQ/Bridge & Structures/Bridge Design/_De	sign Projects/014/BR 14-12/2022_Eme	rgencyRepa	<u>}}_XL6636</u> 6/	_DGN/_Sheets/03 Removal Details 1
	BRIDGE DES. ENG.	LELAND, A				10		
ij	BRIDGE PROJ. ENG.	ROSA, M				10	WASH	75WCDO
Ă	SUPERVISOR	ZELDENRUST, R					JOB NUMBER	
8	DESIGNED BY	BONDY, T	09/22					
	CHECKED BY	DORNSIFE, R	07/23					
	ENTERED BY	TUBBS, N	09/22			C	ONTRACT NO.	
	PRELIM. PLAN BY							
SS	ARCH. / SPEC.			REVISION	DATE	BY		






	PLAN REF I
SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR	В3
EMEROLINO I BRIDGE RELYVIR	SHEET 18 OF
REMOVAL DETAILS	48 SHEETS


PLOT DATE: 7/25/2023


PLOT TIME: 3:42:11 PM

PLOTTED BY: \$\$USERNAME\$\$


<u>SECTION</u>













ᇤ	FILE PATH / NAME	pw://projectstore.wsd	ot.wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Desi	gn Projects/014/BR 14-12/2022	2_Emerger	суRê <del>şçi</del>	XL6636/	DGN/_Shee
뿛	BRIDGE DES. ENG.	LELAND, A					10.		
끯	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	
ĕ	SUPERVISOR	ZELDENRUST, R					J	OB NUMBER	
æ	DESIGNED BY	BONDY, T	09/22						
	CHECKED BY	DORNSIFE, R	07/23						
	ENTERED BY	TUBBS, N	09/22				co	NTRACT NO.	
	PRELIM. PLAN BY								
쫎	ARCH / SPEC			REVISION	D	ATF B	7		







	OF VEHICLE OF WASHINGTON ALL STREET COMMANDED TO THE SHEET COMMAND STREET COMMAND
_	SEE SHEET CT1
	DATE
	P.E. STAMP BOX


	PLAN REF NO
SR 14  LIESER ROAD BRIDGE	В4
EMERGENCY BRIDGE REPAIR	SHEET 19
REMOVAL DETAILS SHEET 2 OF 4	19 OF 48 SHEETS

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:14 PM PLOTTED BY: \$\$USERNAME\$\$




PLOT DATE: 7/25/2023 PLOT TIME: 3:42:17 PM PLOTTED BY: \$\$USERNAME\$\$









- 4									
ᇤ	FILE PATH / NAME	pw://projectstore.wsc	dot.wa.gov:WSDOT/Document	s/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12	/2022_Emer	gency	R&FGGN_	XL <del>662</del> 6/_	DGN/
뛺	BRIDGE DES. ENG.	LELAND, A					10.		1 4
	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	1
ĕl	SUPERVISOR	ZELDENRUST, R					JOB	NUMBER	١ ١
ᇷ	DESIGNED BY	BONDY, T	09/22				]		
[	CHECKED BY	DORNSIFE, R	07/23				]		
	ENTERED BY	TUBBS, N	09/22				CONT	RACT NO.	]
	PRELIM. PLAN BY						]		
쎲	ARCH. / SPEC.			REVISION	DATE	BY	1		

J\_DGN/\_Sheets/06 Removal Details 4




	OF ARIAN SEE SHEET CTI
- 1	DATE
	P.E. STAMP BOX

SR 14	
LIESER ROAD BRIDGE	
EMERGENCY BRIDGE REPAIR	

REMOVAL DETAILS SHEET 4 OF 4 SHEET
21
OF
48
SHEETS

PLAN REF NO

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:21 PM PLOTTED BY: \$\$USERNAME\$\$



# STAGE 4 - CAST CLOSURE POURS & BARRIER

¢ PIER 1


1. CAST LONGITUDINAL DECK CLOSURE, END DIAPHRAGM, AND INTERMEDIATE DIAPHRAGM CLOSURES A MINIMUM OF 10 DAYS AFTER BRIDGE DECK SLAB. SEE SHEETS B12 AND B15. TRAFFIC SHALL BE RESTRICTED TO ONE LANE ALONG THE WEST SIDE OF THE LIESER ROAD BRIDGE WHILE CLOSURE POURS ARE CAST AND A MINIMUM OF 14 DAYS AFTER POURS ARE COMPLETE.

DIAPHRAGM AND ROADWAY SLAB CLOSURE POURS SHALL BE PLACED A MINIMUM OF 10 DAYS AFTER PLACEMENT OF THE ROADWAY SLAB AND PRIOR TO THE TRAFFIC BARRIER.


¢ PIER 2

- 2. CAST STAGE 2 OF HINGE DIAPHRAGM AND TRANSVERSE DECK CLOSURES. SEE SHEET B14. (NOTE: STEP 2 CAN BE CAST THE SAME DAY AS STEP 1 PROVIDED THAT ALL OF THE LONGITUDINAL DECK CLOSURE IS CAST FIRST.)
- 3. CAST BARRIER. SEE SHEETS B19 & B20 FOR DETAILS.

# STAGE 1 - SET GIRDER IN PLACE



# STAGE 2 - CAST DIAPHRAGMS & PLACE SLAB REINF.



# STAGE 3 - CAST ROADWAY SLAB

# STAGE 5

- 1. REINSTALL RAILING ON BARRIER.
- 2. BACKFILL APPROACH AT PIER 1.
- 3. PLACE HMA OVERLAY.
- 4. REMOVE TEMPORARY OAK BLOCKS.
- 5. REMOVE TEMPORARY TRAFFIC BARRIER.

Щ	FILE PATH / NAME	pw://projectstore.wsdot.wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/2	2022_Emergency	<b>₽₽₽₽₽₽</b>	6/ DGN/_Sheets/07 Replacement Sequence
뿘	BRIDGE DES. ENG.	LELAND, A			1 10 1 10	
삤	BRIDGE PROJ. ENG.	ROSA, M			10 WAS	WSDOT
ĕ	SUPERVISOR	ZELDENRUST, R			JOB NUMBER	
8	DESIGNED BY	BONDY, T 09/22			1	
	CHECKED BY	DORNSIFE, R 07/23			1	
	ENTEDED BY	TURRS NI 00/22			CONTRACT NO.	





SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR PLAN REF NO

В7

SHEET 22 of 48

PRELIM. PLAN BY ARCH. / SPEC.

PLOT DATE: 7/25/2023


REPLACEMENT SEQUENCE


REVISION

DATE BY

PLOT TIME: 3:42:24 PM

PLOTTED BY: \$\$USERNAME\$\$






SECTION

# **GROUT PAD DETAIL**

GIRDER NOT SHOWN FOR CLARITY



BEARING DESIGN TA	BLE					
A ASHTO METHOD B DESIG	V					
SERVICE - 1 LIMIT STATE						
DEAD LOAD (DL) REACTION	82 KIPS					
LIVE LOAD REACTION (W/O IMPACT)	41 KIPS					
UNLOADED HEIGHT	1.52 IN					
LOADED HEIGHT (DL)	1.51 IN					
SHEAR MODULUS	165 PSI					


# **NOTES**:


-15°45'00" SKEW ANGLE

- . GIRDER STOP SHALL BE RECONSTRUCTED AFTER GIRDER PLACEMENT.
- 2. UNDAMAGED EXISTING BEARING PADS MAY BE REUSED.

FILE PATH / NAME	pw://projectstore.wsdot.wa.gov	:WSDOT/Documen	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-1:	2/2022_Eme	rgencyR	₹₽₽₽₽   XL <b>663</b> 6/	DGN/_Sheets/08 Girder Bearing Details		*****		PLAN REF NO	.0
場 BRIDGE DES. ENG.	LELAND, A					10.		NI C. LELAN	RD P. ZELDEA	SR 14		
BRIDGE PROJ. ENG.	ROSA, M					10 WASH	75WCDOT	OF WASHING	of WASHING TO	LIESER ROAD BRIDGE	B8	
SUPERVISOR	ZELDENRUST, R					JOB NUMBER		<b>1</b> (\$ 45 <b>3</b> )		EMERGENCY BRIDGE REPAIR		
置 DESIGNED BY	BONDY, T	09/22						any Lectard		ENIEROENO I BRIDOL REI MIR	SHEET	
CHECKED BY	DORNSIFE, R	07/23						39195	1 2 25470 J.		23	
ENTERED BY	TUBBS, N	09/22				CONTRACT NO.		SONAL ENGIN	SONAL ENGINEER		- OF	
PRELIM. PLAN BY								SEE SHEET CT1 DATE	SEE SHEET CT1	REPLACEMENT BEARING PAD DETAILS	48	
ARCH. / SPEC.			REVISION	DATE	BY			P.E. STAMP BOX	P.E. STAMP BOX		SHEETS	

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:27 PM PLOTTED BY: \$\$USERNAME\$\$





# GIRDER END @ PIER 2

MARK LOCATION SIZE NOTE: FOR DIM. "A" SEE GIRDER SCHEDULE 4 GIRDER STIRRUPS G2 GIRDER END STIRRUPS G3 GIRDER TOP FLANGE STR. G4 SIRDER LONGIT. FULL LENGTH STR. G5 GIRDER END LONGIT. STR. G6 GIRDER END TIES GIRDER BOT. FLANGE TIES G9 GIRDER END LONGIT. 4 STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT-TO-OUT)

A"

GI

ALT. SIDES

1'-1½"

GG

1'-6"

\*\* SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE

# #3 OR #4 MAY BE SUBSTITUTED.
FIELD BEND IS OPTIONAL.

C. LEI AND IS OF WASHINGTON ON ALL SEE SHEET OF SEE SHEET

PE STAMP BOX



SR 14

LIESER ROAD BRIDGE

EMERGENCY BRIDGE REPAIR

SHEET
24

W50G GIRDER DETAILS
SHEET 1 OF 3

PLAN REF NC

PLAN REF NC

PLAN REF NC

PLAN REF NC

SHEET
44

SHEET
24


OF
48

SHEETS

FILE PATH / NAME pw://projectstore.wsdot.wa.gov:WSDOT/Documents/\_HQ/Bridge & Structures/Bridge Design/\_Design Projects/014/BR 14-12/2022\_Emergency Refiger \_XL6636/\_DGN/\_Sheets/09 Girder Details 1

BRIDGE DES. ENG. LELAND, A BRIDGE PROJ. ENG. ROSA, M SUPERVISOR ZELDENRUST, R DESIGNED BY 09/22 CHECKED BY DORNSIFE, R 07/23 CONTRACT NO. **ENTERED BY** TUBBS, N PRELIM. PLAN BY ARCH. / SPEC. DATE

**WSDOT** 




GIRDER ELEVATION

C.G. TOTAL STRAIGHT STRANDS

7
1
2"
4 SPA @ 2"=8"
4 SPA @ 2"=8"
2"
C.G. OF HARPED STRAND BUNDLE BETWEEN HARPING POINTS

STRAND PATTERN AT Ç SPAN

STRAND LOCATION SEQUENCE SHALL
BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.

# **KEY NOTES:**


END 2

- 1 PLACE INSERTS ON THE INTERIOR FACE OF GIRDER. PLACE INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4%") FERRULE OR APPROVED EQUAL (TYP.).
- THE NUMBER OF LIFTING STRANDS SHALL BE BASED ON 14 KIPS PER EACH 0.6"Ø STRAND.

<u>[</u>	FILE PATH / NAME	pw://projectstore.wsdot.	wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-:	12/2022_Emergen	cyRefath_XLe6a3e	/_DGN/_Sheets/10 Girder Details 2				PLAN REF NO
뿛[	BRIDGE DES. ENG.	LELAND, A				10 1/40		N C. LELAN	RD P. ZELDEN	SR 14	
ij	BRIDGE PROJ. ENG.	ROSA, M				10 WASH	75WCDOT	of Washing	St. OF WASHING	LIESER ROAD BRIDGE	B10
ĕΙ	SUPERVISOR	ZELDENRUST, R				JOB NUMBER		1 (5 April 9)		EMERGENCY BRIDGE REPAIR	
器[	DESIGNED BY	BONDY, T	09/22					any Lectard		EIVIEROEINO I BRIDOL REI / IR	SHEET
	CHECKED BY	DORNSIFE, R	07/23					39195	10 25470 J.S.		25
	ENTERED BY	TUBBS, N	09/22			CONTRACT NO.		SONAL ENGIN	SSIONAL ENGINEER		- of
	PRELIM. PLAN BY							SEE SHEET CT1	SEE SHEET CT1	W50G GIRDER DETAILS	48
8	ARCH. / SPEC.			REVISION	DATE B'			P.E. STAMP BOX	P.E. STAMP BOX	SHEET 2 OF 3	SHEETS


PLOT DATE: 7/25/2023 PLOT TIME: 3:42:34 PM PLOTTED BY: \$\$USERNAME\$\$

END 1



# TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




# END OF P.S. GIRDER\_

# **SAWTOOTH DETAILS**


SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W50G GIRDER DETAILS 1 OF 3



# **ELEVATION**



<u>PLAN</u> BEARING RECESS @ PIER 1



# PLAN - BOTTOM FLANGE SPALL PROTECTION

# GIRDER SCHEDULE

	DIMENSION "A" AT Ç BEARINGS = 8"									BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)										
									MIN. CONC. COMPR. STRENGTH		HARPED		STRAIGHT		LOCATION OF				S	S
	SPAN GIRDER END 1 TYPE	'nE	PE	$\Theta_{i}$					TINAL I KSI ILEASE I KSI						STRA	NDS		ΑΥ	ΑΥ	
Z		I–I	ı⊢ı		Θ <sub>2</sub>	$\Theta_2$ $P_1$	P <sub>2</sub>	PLAN LENGTH (ALONG GIRDER		KS	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	Е	Fb	Fo	υĺ	40 D (IN)	120 C (IN)
SP	GIR	ENC	EN					GRADE)	@ F	@ REL F'CI		(K1F3)		(KIPS)					@ _	(a)
1	G	Α	С	74°	74°	14'-11/8"	N/A	100'-91/8"	8.5	7.5	10	439	12	527	2.67"	4"	8"	3/4"	1"	2.25"

Щ	FILE PATH / NAME	pw://projectstore.wsdot.wa.gov:WSDOT/Documen	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/20	:022_Emerge	ency Re	GION .	XL <del>6</del> 636/_	DGN/_Sheets/11 Girder Details 3
뚨	BRIDGE DES. ENG.	LELAND, A				4.0		
	BRIDGE PROJ. ENG.	ROSA, M				10	WASH	
ĕ	SUPERVISOR	ZELDENRUST, R				JOB I	NUMBER	<b>MM M2DO I</b>
쁊	DESIGNED BY	BONDY, T 09/22						
	CHECKED BY	DORNSIFE, R 07/23						
	ENTERED BY	TUBBS, N 09/22				CONTR	RACT NO.	
اِ	PRELIM. PLAN BY							

REVISION





SR 14	
LIESER ROAD BRIDGE	
EMERGENCY BRIDGE REPAIR	

W50G GIRDER DETAILS

SHEET 3 OF 3


26 OF 48 SHEETS

PLAN REF NO B11


ARCH. / SPEC. PLOT DATE: 7/25/2023

PLOT TIME: 3:42:37 PM


PLOTTED BY: \$\$USERNAME\$\$



**ELEVATION - END DIAPHRAGM** 











- CLOSURE IN END DIAPHRAGM TO BE CAST WITH LONGITUDINAL DECK CLOSURE
- 2 MATCH EXISTING DIAPHRAGM AT CONSTRUCTION JOINT

- 4									
ᇤ	FILE PATH / NAME	pw://projectstore.wsd	lot.wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/B	R 14-12/2022_Emer	rgency	R&FGGON_	XL <del>663</del> 6/_	DGI
뛺	BRIDGE DES. ENG.	LELAND, A					10.	) . ( A OL I	
ij	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	
	SUPERVISOR DESIGNED BY	ZELDENRUST, R					JOB	NUMBER	
ᇷ	DESIGNED BY	BONDY, T	09/22						
[	CHECKED BY	DORNSIFE, R	07/23						
	ENTERED BY	TUBBS, N	09/22				CONT	RACT NO.	
	PRELIM. PLAN BY								
炎	ARCH. / SPEC.	•		REVISION	DATE	BY			
	DLOT DATE. 7/25/20	DIOT TIM	IE. 2.40.40 DM	DI OTTED DV. ##LICEDNAME##					



DETAIL





SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR


END DIAPHRAGM

SHEET

PLAN REF NO


B12

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:40 PM PLOTTED BY: \$\$USERNAME\$\$




DATE BY

NOTE: NO CLOSURE REQUIRED IN PIER 1 DIAPHRAGM









- 1							
ᇤ	FILE PATH / NAME	pw://projectstore.wsdot.wa.gov:WSDOT/Documen	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/	/2022_Emerge	encyReFoli	N_XL6626/.	DGN/_Sheets/13 Pier 1 Diaphragm
뿛	BRIDGE DES. ENG.	LELAND, A			10	). (A OLI	
ij	BRIDGE PROJ. ENG.	ROSA, M			10	WASH	
ĕ	SUPERVISOR	ZELDENRUST, R			J	OB NUMBER	
8	DESIGNED BY	BONDY, T 09/22					
	CHECKED BY	DORNSIFE, R 07/23					
	ENTERED BY	TUBBS, N 09/22			cc	NTRACT NO.	
	PDFI TM PLAN RY						

REVISION





	W ARITON WASHINGTON WA	
1	SEE SHEET CT1	
_	DATE	


SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR


PIER 1 DIAPHRAGM

SHEET 28 OF 48 SHEETS

PLAN REF NO B13


ARCH. / SPEC. PLOT DATE: 7/25/2023 PLOT TIME: 3:42:43 PM PLOTTED BY: \$\$USERNAME\$\$






**ELEVATION - PIER 2 HINGE** 

DATE BY






# SECTION

# **KEY NOTES:**

- 1 THE CONTRACTOR SHALL SUBMIT AN EXISTING GIRDER STABILIZATION PLAN FOR APPROVAL BY THE ENGINEER. THE TEMPORARY SUPPORT SHOWN IS A SUGGESTION ONLY.
- 2 MEASURED NORMAL TO © PIER 2.
- 3 CAST STAGE 2 OF HINGE DIAPHRAGM WITH TRANSVERSE DECK CLOSURE.

- 1							
	FILE PATH / NAME	pw://projectstore.wsdot.wa.gov:WSDOT/Documen	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/	2022_Emergenc	у Керсин	XL6626/	DGN/_Sheets/14 Hinge Diaphragm At Pier 2
뿘	BRIDGE DES. ENG.	LELAND, A			10	). (A OLI	
	BRIDGE PROJ. ENG.	ROSA, M			10	WASH	75WCDOT
ĕ	SUPERVISOR DESIGNED BY	ZELDENRUST, R			JO	B NUMBER	
æ	DESIGNED BY	BONDY, T 09/22					
	CHECKED BY	DORNSIFE, R 07/23					
	ENITEDED BY	TURRS N 00/00			CON	ITRACT NO.	]

REVISION





SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR

PLAN REF NO B14

> SHEET 29 OF 48 SHEETS


HINGE DIAPHRAGM AT PIER 2


ARCH. / SPEC. PLOT DATE: 7/25/2023

PRELIM. PLAN BY


PLOT TIME: 3:42:47 PM


PLOTTED BY: \$\$USERNAME\$\$






# **ELEVATION - INTERMEDIATE DIAPHRAGM**








# TYPICAL SECTION THROUGH GIRDER OPTION 2 PRE-BENT G1 #5 STIRRUPS WITH #5 HAT BAR

## NOTES:

- 1 CLOSURE IN INTERMEDIATE DIAPHRAGM TO BE CAST WITH LONGITUDINAL DECK CLOSURE.
- 2 H1 ♥ #5 HAT BAR MAY BE OMITTED AT LOCATIONS WHERE GIRDER STIRRUPS PROJECT AT LEAST 3" ABOVE THE BOTTOM OF THE TRANSVERSE BAR IN THE BOTTOM MAT OF THE BRIDGE DECK.

# BENDING DIAGRAM

ALL DIMENSIONS ARE OUT-TO-OUT



OPTION 2 ~ H1 ♥ #5 HAT BAR

PLAN REF NO B15

> SHEET 30 of 48


ᇤ	FILE PATH / NAME	pw://projectstore.wsdot.wa.gov:WSDOT/Documen	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12/	/2022_Emerg	encyRep	?P_XL66636	/_DGN/_Sheets/15 Intermediate Diaphragm
뿛	BRIDGE DES. ENG.	LELAND, A			1		
	BRIDGE PROJ. ENG.	ROSA, M			10	WASH	75WCDOT
	SUPERVISOR	ZELDENRUST, R				JOB NUMBER	
쁊	DESIGNED BY	BONDY, T 09/22					
	CHECKED BY	DORNSIFE, R 07/23					
	ENTERED BY	TUBBS, N 09/22			0	ONTRACT NO.	

REVISION

OPTION 1 FIELD BEND GIRDER STIRRUPS

DATE





SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR


INTERMEDIATE DIAPHRAGM

ARCH. / SPEC. PLOT DATE: 7/25/2023

PRELIM. PLAN BY

PLOT TIME: 3:42:50 PM

PLOTTED BY: \$\$USERNAME\$\$




# SLAB PLAN - TOP MAT REINFORCEMENT

# NOTES:

1 REINFORCEMENT TYPICAL BETWEEN GIRDERS

2. LAP SPLICE LENGTHS: #4 BARS TO #4, #9, OR #10 = 2'-0" #5 BARS TO #5 = 2'-4" #9 BARS TO #9, OR #10 = 4'-3" #7 BARS TO #9 = 3'-3"



# SCREED SETTING DIMENSIONS

FOR DIMENSION "C" SEE GIRDER SCHEDULE

ᇤ	FILE PATH / NAME	pw://projectstore.wsdo	t.wa.gov:WSDOT/Document	ts/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12.	/2022_Emer	gency	Zeegan_	XL <del>6626</del> /_	DGI
뛿	BRIDGE DES. ENG.	LELAND, A					40	) . ( A OL I	1
끯	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	
ĕ	SUPERVISOR	ZELDENRUST, R					JOB	NUMBER	
盎	DESIGNED BY	BONDY, T	09/22						
	CHECKED BY	DORNSIFE, R	07/23						
	ENTERED BY	TUBBS, N	09/22				CONT	RACT NO.	
	PRELIM. PLAN BY								
SS	ARCH. / SPEC.			REVISION	DATE	BY			





	OF WASHINGTON AND STREET COMMANDED TO STREET COMMAND STREET COMMAN
_	SEE SHEET CT1
	DATE
	P.E. STAMP BOX


SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR

SLAB PLAN SHEET 1 OF 2 PLAN REF NO

B16

31 OF 48 SHEETS

PLOT DATE: 7/25/2023 PLOT TIME: 3:42:53 PM PLOTTED BY: \$\$USERNAME\$\$



# **SLAB PLAN - BOTTOM MAT REINFORCEMENT**

BRIDGE DES. ENG. LELAND, A BRIDGE PROJ. ENG. ROSA, M SUPERVISOR ZELDENRUST, R DESIGNED BY BONDY, T 09/22 CHECKED BY DORNSIFE, R 07/23 CONTRACT NO. ENTERED BY TUBBS, N PRELIM. PLAN BY G ARCH. / SPEC. DATE BY







SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR


> SLAB PLAN SHEET 2 OF 2

PLAN REF NO


B17

SHEET

PLOT TIME: 3:42:57 PM PLOT DATE: 7/25/2023 PLOTTED BY: \$\$USERNAME\$\$



PLAN - TOP SLAB REINFORCEMENT MECHANICAL COUPLER DETAIL



SLAB REINFORCEMENT
SHOWN NEAR PIER 2

I,									
ᇤ	FILE PATH / NAME BRIDGE DES. ENG.	pw://projectstore.wsdo	ot.wa.gov:WSDOT/Document	s/_HQ/Bridge & Structures/Bridge Design/_Design Projects/014/BR 14-12.	'2022_Emer	gency	Reform_	XL <del>663</del> 6/_	DGI
뚨	BRIDGE DES. ENG.	LELAND, A					40	) . ( A OL I	l
띥	BRIDGE PROJ. ENG.	ROSA, M					10	WASH	j
ĕ	SUPERVISOR DESIGNED BY	ZELDENRUST, R					JOB	NUMBER	l
盎	DESIGNED BY	BONDY, T	09/22						İ
	CHECKED BY	DORNSIFE, R	07/23						İ
	ENTERED BY	TUBBS, N	09/22				CONT	RACT NO.	l
	PRELIM. PLAN BY								l
Ŗ	ARCH. / SPEC.			REVISION	DATE	BY			







SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR


PLAN REF NO


B18


33 OF 48 SHEETS


SLAB REINFORCEMENT

PLOT DATE: 7/25/2023 PLOT TIME: 3:43:01 PM PLOTTED BY: \$\$USERNAME\$\$










MULTIPLE STRAND REPAIR


4 EPOXY INJECT CRACKS IN GIRDERS AS DIRECTED BY THE ENGINEER.

PORTS ON BOTH SIDES OF THE GIRDER AT 6" SPACING

5 PERFORM FULL-DEPTH EPOXY INJECTION. PLACE INJECTION PORTS AND VENT




# EXISTING GIRDER ELEVATION



# ORDER OF GIRDER REPLACEMENT AND GIRDER REPAIR WORK:

- 1. REMOVE AND REPLACE GIRDER 1G.
- 2. ON GIRDERS 1A 1F, REMOVE DAMAGED AND UNSOUND CONCRETE TO THE LIMITS SHOWN OR AS DIRECTED BY THE ENGINEER. PROVIDE 3/4" SAWCUT AT ALL EDGES OF THE REPAIR. CONCRETE SHALL BE REMOVED AROUND ALL EXPOSED REBAR AND STRANDS TO PROVIDE A MINIMUM OF 1" CLEARANCE AROUND THE BAR OR STRAND FOR CONCRETE PLACEMENT.
- 3. ON GIRDER 1A, CUT DAMAGED STRANDS AS REQUIRED FOR THE APPROVED CABLE SPLICE. LUBRICATE AND INSTALL CABLE SPLICES PER THE MANUFACTURER'S RECOMMENDATIONS. THE CONTRACTOR SHALL BEGIN WITH THE INNERMOST STRAND AND PROGRESS OUTWARD TOWARD EXTERIOR FACE OF THE GIRDER. TORQUE THE CABLE SPLICE TO THE LUBRICATED TORQUE VALUE, AS SPECIFIED BY THE SPLICE MANUFACTURER, TO PROVIDE A FORCE OF 10 KIPS IN EACH SPLICED STRAND.
- 4. ON GIRDERS 1A 1F, NEEDLE SCALE OR SANDBLAST RUST FROM CORRODED REBAR AND APPLY RUST INHIBITOR PER MANUFACTURER'S RECOMMENDATIONS.
- 5. ON GIRDERS 1A 1F, INSTALL PATCH PINS 4" ON CENTER EACH WAY WITH 2" MAXIMUM EDGE DISTANCE. DRILL FOR AND INSTALL PATCH PINS PER MANUFACTURER'S RECOMMENDATIONS.
- 6. ON GIRDER 1A, PLACE FORMWORK AND POUR GIRDER REPAIR CONCRETE. GIRDER REPAIR CONCRETE SHALL BE CLASS 6000. DURING PLACEMENT OF THE GIRDER REPAIR CONCRETE ON GIRDER 1A, AND DURING THE FOLLOWING 24 HOURS, TRAFFIC SHALL BE RESTRICTED TO ONLY ONE LANE ALONG THE EAST SIDE OF THE LIESER ROAD BRIDGE.
- 7. ON GIRDERS 1B 1F, APPLY EPOXY CONCRETE BONDING AGENT TO SPALL AREA. APPLY APPROVED PATCHING MATERIAL BEFORE EPOXY BONDING AGENT TAKES INITIAL SET. EPOXY BONDING AGENT SHALL BE PER WSDOT STANDARD SPECIFICATIONS 9-26.1(1)B.
- 8. ON GIRDER 1A, PERFORM FULL-DEPTH EPOXY INJECTION ON THE 40' LONG CRACK AT THE INTERFACE BETWEEN THE TOP FLANGE AND THE WEB. PLACE INJECTION PORTS AND VENT PORTS ON BOTH SIDES OF THE GIRDER AT 6" SPACING.
- 9. ON GIRDERS 1A 1F, EPOXY INJECT ALL CRACKS AS DIRECTED BY THE ENGINEER.

SUPERVISOR	LIESER ROAD BRIDGE B2
ENTERED BY TUBBS N 09/22 CONTRACT NO.	EMERGENCY BRIDGE REPAIR
PRELIM. PLAN 01  DATE  DATE	DATE P.E. STAMP BOX  GIRDER REPAIR DETAILS  GIRDER REPAIR DETAILS  48 SHEET



							QL	JANTI	TY TA	BULA	ATION	- PA	/EME	NT M	ARKIN	NG PL	.AN				
TO THE S SHOWING THE SEC	T NUMBER OF THE "CC HEET NO. OR THE SHE S THE CONSTRUCTION DND NUMBER REFERS ICTION FEATURE FOU!	ET REFERI FEATURE TO THE	ENCE NO.	PAINT LINE - DOUBLE CENTERLINE	PAINT LINE - EDGE LINE	PAINT LINE - DOTTED EXTENSION LINE		PLASTIC LINE - STOP LINE 24"		PLASTIC CROSSWALK LINE		PLASTIC DRAINAGE MARKING		RAISED PAVEMENT MARKER - TYPE 2					GENERAL NOTES		
CODE	LOCATION ↓ / UNI			LF	LF	LF		LF		SF		EA		HUND						GENERAL NOTES	
	STA 8+56 (0' RT) TC STA 7+00 (0' RT) TC			285 66															1	1. See STD PLN M-20.10 FOR LONGITUDINAL MARKING PATTERNS	
MK1-4	STA 7+00 (12' RT) TC STA 7+00 (12' LT) TC	O STA 7+6	66 (12' LT)		440 66														1	2. See STD PLN M-24.60 FOR DRAINAGE MARKIN	NG
	STA 8+56 (12' LT) TO				283	00													1	2 C - C' - CV CV	
MK1-6 MK1-7	STA 7+66 (12' LT) TO STA 7+66 (0' LT) TO					99													1	3. See City of Vancouver STD PLN T29-48 FOR RAISED PAVEMENT MARKER	
MK1-8	STA 11+39 (0' RT) TC	) STA 11+3	39 (12' RT)					12											1	4. See STD PLN M-15.10 FOR CROSSWALK	
	STA 8+00 (16' LT) To	O STA 8+1	.4 (21' LT)							260									4		
	STA 8+90 (13' LT) STA 9+04 (13' RT)											1	-						2		
	STA 10+20 (13' RT)											1							2	-	
	STA 10+25 (13' LT)											1							2		
MK1-14	START AT STA 11+3	36 (0' RT)												0.1					3		
MK1-15	STA 9+30 (13' LT)											1							2		
	PROJECT TOTAL			351	789	190		12		260		5		0.10							
								REGION NO.	STATE	FED. AID	PROJ. NO.									SR 14	QT2
Designed Entered	R. GREGORIO CGAEO							10	WASH						<u> </u>	Unahin eta-	Chata			LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR	SHEET
	T. HARTMANN M. BRIGGS							4	UMBER (347	ER-STBG	-2C05001					Washingtor Departmen	t of Trans	portation			38 <b>OF</b>
	C. FRANCIS	DATE	DATE		REVISION		BY		ACT NO.											QUANTITY TABULATION	48 SHEETS

(	GUARDRAIL SCHEDULE	
	BEAM GUARDRAIL TRANSITION SECTION TYPE 24	BEAM GUARDRAIL TYPE 31
LOCATION	EACH	L.F.
STA. 9+00	1	
STA. 8+98.73 TO STA. 7+61.23		137.5

#### GENERAL NOTES:

- 1. INSTALL BEAM GUARDRAIL CONNECTION TO STRUCTURE ADAPTER PLATE PER STD PLN C-24.15.
- 2. INSTALL GUARDRAIL CONNECTION B TO BRIDGE TRAFFIC BARRIER PER STD. PLN. C-24.10.
- 3, INSTALL BEAM GUARDRAIL TRANSITION SECTION TYPE 24 PER STD PLN C-25,30,
- 4. INSTALL BEAM GUARDRAIL TYPE 31 TO BEAM GUARDRAIL TYPE 1 ADAPTOR PER STD. PLN C-25.80.

#### NOTES:

- 1. STOP LINE SHALL BE 24" WIDE PLASTIC (EITHER TYPE A OR B).
- 2. RAISED PAVEMENT MARKERS ARE AT 40' SPACING. SEE CITY OF VANCOUVER STD. PLN. T29-48.
- 3. SEE SHEET QT2 FOR QUANTITY TABULATION.

#### LEGEND:

QUANTITY TAB REFERENCE

# CONSTRUCTION NOTE

DOUBLE CENTERLINE NEW (Y)

EDGLE LINE NEW (W)

DOTTED EXTENSION LINE NEW (Y)

DOTTED EXTENSION LINE NEW (W)

STOP LINE NEW

111111 CROSSWALK LINE NEW

PLASTIC DRAINAGE MARKING NEW

BEAM GUARDRAIL NEW

RAISED PAVEMENT MARKER NEW

SHOULDER PAVED EDGE EXISTING

DOUBLE CENTERLINE EXISTING

EDGE LINE EXISTING

LANE LINE EXISTING

BARRIER EXISTING

STOP LINE EXISTING ----

STORM DRAIN INLET EXISTING

YELLOW

W WHITE

## CONSTRUCTION NOTES:

PAINT LINE - DOUBLE CENTERLINE (Y)

PAINT LINE - EDGE LINE (W)

PAINT LINE - DOTTED EXTENSION LINE (Y)

PAINT LINE - DOTTED EXTENSION LINE (W)


PLASTIC STOP LINE - 24"

PLASTIC CROSSWALK LINE

PLASTIC DRAINAGE MARKING

RAISED PAVEMENT MARKER - TYPE 2

BEAM GUARDRAIL (ASSEMBLY)



FILE NAME	G:\444302\03 - Design\D01422	G SR	14 Lieser Rd	Br - Emergency	Br Repair\20-CADD	-Plans\20-2	PS&E	Sheets\	D014220	S_PS_MKRD_GUARDRAIL AND	ī
TIME	4:54:12 PM							REGION NO.	STATE	FED.AID PROJ.NO.	1
DATE	6/15/2023							10	WASH	ER-STBG-2C05001	
PLOTTED BY	GregorR							יי ן	WASH		1/3
DESIGNED BY	R. GREGORIO								IUMBER		1/3
ENTERED BY	CGAEO							22X	347		ľ
CHECKED BY	T. HARTMANN							CONTR	RACT NO.	LOCATION NO.	1
PROJ. ENGR.	M. BRIGGS							1		XL6636	
REGIONAL ADM.	C. FRANCIS			REVISION		DATE	BY	1		AL0030	1





Washington State
Department of Transportation


SR 14
LIESER ROAD BRIDGE
EMERGENCY BRIDGE REPAIR


Plot 1

MK1

39

GUARDRAIL AND PAVEMENT MARKING





TEMPORARY SIGN LOCATION

TRAFFIC SAFETY DRUM

TEMPORARY SIGN LOCATION (5'MIN HEIGHT)

SEQUENTIAL ARROW SIGN




TRANSPORTABLE ATTENUATOR


#### NOTES:

- 1. SHOULDER CLOSURE VALID FOR DOUBLE-LANE OR MULTI-LANE ROADWAYS.
- 2. DEVICE SPACING FOR THE DOWNSTREAM TAPER SHALL BE 20'(FT)
- 3. CONTRACTOR SHALL SHUTTLE BICYCLE TRAFFIC AROUND/THRU WORK ZONE, AS NEEDED.

# SHOULDER CLOSURE - HIGH SPEED NOT TO SCALE

REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		1 7123030	P.E. STAMP BOX	P.E. STAMP BOX		I III I I I I I I I I I I I I I I I I	5.1.22.10
PROJ. ENGR.	M. BRIGGS					XL6636	DATE	DATE	-	TRAFFIC CONTROL PLANS	48 SHEETS
CHECKED BY	T. HARTMANN				CONTRACT NO.	LOCATION NO.	1		Department of Transportation		OF OF
ENTERED BY	CGAEO				22X347				3		41
DESIGNED BY	R. GREGORIO				JOB NUMBER	1			Washington State	EMERGENCY BRIDGE REPAIR	SHEET
PLOTTED BY	GregorR				IU WASF	]				LIESER ROAD BRIDGE	1 '5'
DATE	6/15/2023				10 WASH	ER-STBG-2C05001					TC1
TIME	10:55:09 AM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
FILE NAME	G:\444302\03 - Design\D01422G SR 14 Lieser Rd B	r - Emergency Br Repair\20-CADD-I	Plans\20-2 P				PLANS.dgn				Plot 1





- TEMPORARY SIGN LOCATION
- TRAFFIC SAFETY DRUM
- TEMPORARY SIGN LOCATION (5'MIN HEIGHT)

SEQUENTIAL ARROW SIGN

TRANSPORTABLE ATTENUATOR

# FREEWAY: SINGLE RIGHT LANE CLOSURE (EXIT-RAMP OPEN) NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D014226	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD-	-Plans\20-2 P	S&E	Sheets\l	D014220	S_PS_TC_TRAFFIC CONTROL	PLANS.dgn
TIME	10:59:25 AM				REGION	STATE	FED.AID PROJ.NO.	1
DATE	6/15/2023				10	WASH	ER-STBG-2C05001	1
PLOTTED BY	GregorR				10	WASH		1
DESIGNED BY	R. GREGORIO				JOB N			1
ENTERED BY	CGAEO				22X	347		
CHECKED BY	T. HARTMANN				CONTRA	ACT NO.	LOCATION NO.	1
PROJ. ENGR.	M. BRIGGS				1		XL6636	DATE
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY	1		AL0030	P.E. STAMP BOX



NOTES:

SR 14
LIESER ROAD BRIDGE
LILOLIN NOAD BRIDGE
EMERGENCY BRIDGE REPAIR

TRAFFIC CONTROL PLANS

1. IF USED, PLACE DEVICES TRANSVERSELY ACROSS CLOSED LANES

3. CONTRACTOR SHALL SHUTTLE BICYCLE TRAFFIC AROUND/THRU

AT 45° +/- AND 5' SPACING AT STRATEGIC LOCATIONS.


2. DOWNSTREAM TAPER OPTIONAL ACROSS LEFT LANE.


DOWNSTREAM TAPER DEVICE SPACING IS 20'.

WORK ZONE, AS NEEDED.

42 of 48 sheets

Plot 2 PLAN REF NO TC2





TEMPORARY SIGN LOCATION

TRAFFIC SAFETY DRUM

TEMPORARY SIGN LOCATION (5'MIN HEIGHT)

>>> SEQUENTIAL ARROW SIGN

TRANSPORTABLE ATTENUATOR

#### NOTES:

- 1. IF USED, PLACE DEVICES TRANSVERSELY ACROSS CLOSED LANES AT 45° +/- AND 5' SPACING AT STRATEGIC LOCATIONS.
- 2. DOWNSTREAM TAPER OPTIONAL ACROSS LEFT LANE. DOWNSTREAM TAPER DEVICE SPACING IS 20'.
- 3. CONTRACTOR SHALL SHUTTLE BICYCLE TRAFFIC AROUND/THRU WORK ZONE, AS NEEDED.


# FREEWAY: SINGLE LEFT LANE CLOSURE

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD	-Plans\20-2 PS	S&E SI	heets\D01422	G_PS_TC_TRAFFIC CONTROL	PLANS.dgn					
TIME	11:02:21 AM				REGION STATE	FED.AID PROJ.NO.	1			SR 14	PLAN REF NO	10
DATE	6/15/2023				10 WASH	ER-STBG-2C05001					TC3	
PLOTTED BY	GregorR				10 WASI	]				LIESER ROAD BRIDGE	103	
DESIGNED BY	R. GREGORIO				JOB NUMBER				Washington State	EMERGENCY BRIDGE REPAIR	SHEET	П
ENTERED BY	CGAEO				22X347				3		43	
CHECKED BY	T. HARTMANN				CONTRACT NO.	LOCATION NO.			Department of Transportation		OF	
PROJ. ENGR.	M. BRIGGS					XL6636	DATE	DATE		TRAFFIC CONTROL PLANS	48 SHEETS	
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		AEGGGG	P.E. STAMP BOX	P.E. STAMP BOX			SHEETS	

PCN	IS 1
1	2
WATCH	NEXT
FOR SLOW	#
TRAFFIC	MILES
2.0 SEC	2.0 SEC

	PCMS 2	
1	2	3
SR 14	LIESER	USE
CLOSED	CLOSED	ALT
AHEAD	AHEAD	ROUTE
1.5 SEC	1.5 SEC	1.5 SEC



- ▶ TEMPORARY SIGN LOCATION
- ► TEMPORARY SIGN LOCATION (5'MIN HEIGHT)
- TRAFFIC SAFETY DRUM

SEQUENTIAL ARROW SIGN

TRANSPORTABLE ATTENUATOR

PCMS

PORTABLE CHANGEABLE MESSAGE SIGN

TYPE III BARRICADE

# SR 14 FULL CLOSURE - ALL TRAFFIC MUST EXIT

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD	-Plans\20-2 P	S&E	Sheets\D01422	G_PS_TC_TRAFFIC CONTROL	PLANS.dgn
TIME	11:05:54 AM				REGION STATE	FED.AID PROJ.NO.	
DATE	6/15/2023				10 WASH	ER-STBG-2C05001	
PLOTTED BY	GregorR				IU WASE	1	
DESIGNED BY	R. GREGORIO				JOB NUMBER	1	
ENTERED BY	CGAEO				22X347		
CHECKED BY	T. HARTMANN				CONTRACT NO.	LOCATION NO.	
PROJ. ENGR.	M. BRIGGS				1	XL6636	DATE
REGIONAL ADM	C. FRANCIS	REVISION	DATE	BY	1	1 712000	DE STAMP BOY

Washington State
Department of Transportation

DATE

NOTES:

SIGNING.

SR 14 LIESER ROAD BRIDGE EMERGENCY BRIDGE REPAIR

1. THE CONTRACTOR SHALL COVER EXISTING CLASS A SIGNS

2. CONTRACTOR SHALL SHUTTLE BICYCLE TRAFFIC AROUND/THRU

3. FIELD LOCATE PCMS 1 MILE IN ADVANCE OF LANE CLOSURE

AS DIRECTED BY THE ENGINEER.


WORK ZONE, AS NEEDED.


SHEET 44 OF 48 SHEETS

Plot 4

TC4

TRAFFIC CONTROL PLANS





TEMPORARY SIGN LOCATION

DIRECTION OF TRAVEL

PCMS PORTABLE CHANGEABLE MESSAGE SIGN


TYPE III BARRICADE


LIESER BRIDGE FULL CLOSURE

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422	G SR 14 Lieser Rd Br - Emergency Br Repair\20-CADD	-Plans\20-2 I	PS&E	Sheets\D01422	G_PS_TC_TRAFFIC CONTROL	PLANS.dgn				Plot 6
TIME	11:15:49 AM				REGION STATE	FED.AID PROJ.NO.				SR 14	PLAN REF NO
DATE	6/15/2023				40 WASI	ER-STBG-2C05001					TC6
PLOTTED BY	GregorR				IU WASE					LIESER ROAD BRIDGE	100
DESIGNED BY	R. GREGORIO				JOB NUMBER	1			Washington State	EMERGENCY BRIDGE REPAIR	SHEET
ENTERED BY	CGAEO				22X347				, ,		46
CHECKED BY	T. HARTMANN				CONTRACT NO.	LOCATION NO.			Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS					XL6636	——————————————————————————————————————	DATE		TRAFFIC CONTROL PLANS	48 SHEETS
REGIONAL ADM.	C. FRANCIS	REVISION	DATE	BY		A20030	P.E. STAMP BOX	P.E. STAMP BOX			SHEETS

SIGN SPACING	= X (1)	
RURAL ROADS	45 / 55 MPH	500'
RURAL ROADS & URBAN ARTERIALS	35 / 40 MPH	350'
RURAL ROADS & URBAN ARTERIALS	25 / 30 MPH	200' (2)
RESIDENTAL & BUSINESS DISTRICTS		
URBAN STREETS	25 MPH OR LESS	100' (2)
(1) ALL SPACING MAY BE ADJUSTED TO INTERCHANGE RAMPS, AT-GRADE INTERS	ACCOMMODATE ECTIONS AND DRIVE	WAYS.
(2) THIS SPACING MAY BE REDUCED IN ROADWAY CONDITIONS.	URBAN AREAS TO	FIT





- TEMPORARY SIGN LOCATION
- TRAFFIC SAFETY DRUM
- TRAFFIC CONE

र । विद्यासा FLAGGING STATION

**♦** ₹

PROTECTIVE VEHICLE
DIRECTION OF TRAVEL

# UNSIGNALIZED INTERSECTING ROADWAY DETAIL

#### NOTES:

- 1. INSTALL SIGN W20-7B ON OFF-RAMP AS PART OF SIGN SEQUENCE A.
- TYPICAL APPLICATION SHOWN, ADJUST FOR SITE CONDITIONS. MAY UTILIZE SHEET TC7 FOR GUARDRAIL REPLACEMENT WORK.
- 2. NIGHT WORK REQUIRES ADDITIONAL ROADWAY LIGHTING AT FLAGGING STATIONS, SEE STANDARD SPECIFICATIONS FOR ADDITIONAL DETAILS.
- 3. 36" TRAFFIC CONES, 42" TALL CHANNELIZATION DEVICES, OR TRAFFIC SAFETY DRUMS OK.
- 4 PAVEMENT MARKINGS MAY VARY.

# FLAGGING OPERATION

NOT TO SCALE

FILE NAME	G:\444302\03 - Design\D01422G SR 14 Lieser Rd Br - Emergency Br Repair\20-CAD	D-Plans\20-2	PS&E	Sheets\D0142	G_PS_TC_TRAFFIC CONTROL	_PLANS.dgn				Plot 7
TIME	11:40:38 AM			REGION STATE	LED'AID LUG'INO	1			SR 14	PLAN REF NO
DATE	6/15/2023			10 WAS	ER-STBG-2C05001				<u> </u>	TC7
PLOTTED BY	GregorR			I IU WAS					LIESER ROAD BRIDGE	
DESIGNED BY	R. GREGORIO			JOB NUMBER				Washington State	EMERGENCY BRIDGE REPAIR	SHEET
ENTERED BY	CGAEO			22X347				3		47
CHECKED BY	T. HARTMANN			CONTRACT NO.	LOCATION NO.	1		Department of Transportation		OF
PROJ. ENGR.	M. BRIGGS				XL6636	DATE	DATE	_	TRAFFIC CONTROL PLANS	48 SHEETS
REGIONAL ADM.	C. FRANCIS REVISION	DATE	BY		/L3030	P.E. STAMP BOX	P.E. STAMP BOX			J. STIZETS

