


		can be planning, scoping or design teams	typically design teams preliminary engineering	final design and contract documents (ps&e) development			transition to construction	
				geometric design review (design approval)	constructability review	pre-contract review		
contents	consult or discuss with			~30%	~60%	~90%	100%	
1 Timeline actions and purpose								
2 Project Management								
3 Cost Estimates								
4 Environmental Review, Permitting & Documentation								
5 Cost Risk Estimating Management								
6 Value Engineering								
7 Pavement								
8 Utilities and Railroad								
9 Access – limited/managed								
10 Right-Of-Way								
11 Community Engagement								
12 Design Documentation								
13 Roadway Geometrics and Plans								
14 Channelization and Pavement Marking Plans								
15 Hydraulics-Water Quality								
16 Survey & Mapping								
17 Structures, Bridges, et al								
18 Illumination, signals and ITS								
19 Geotechnical Recommendations								
20 Work Zone Traffic Control								
21 Traffic Analysis								
22 Safety Analysis								
23 Signing								
24 Temporary Erosion and Sediment Control (TESC)								
25 Specifications								
26 Maintenance								

LEGEND

Blue shading = a new row, added since the last deliverables expectations matrix
Orange shading = if applicable these groups/activities may be involved at these times in your project
Orange pattern = sometimes these activities are happening during this time frame



Deliverables Expectation Matrix

Communicates typical expectations for project deliverables and helps establish mutual understanding of these expectations.

Provides a “schematic” of the Project Development Process at WSDOT - The matrix is foundational to seasoned project managers, project teams, staff and our consultant partners. The matrix offers additional value as a guide for staff learning how to complete a WSDOT project.

This tool is used to help plan and execute work for project development. The matrix offers Quality Control, Quality Assurance and Quality Verification benefits. The matrix helps team readiness for project reviews and organizes the project development process as follows:

Planning (corridor sketch strategies)

Scoping

Pre 30%

Geometric design review / design approval (~ 30% design level)

Constructability review (~60 design level)

Pre-contract review (~90% design level)

Contract documents ready (~100% design level)

Contract ad and award

Design Phase Close Out

[Deliverables Expectation Matrix](#)

[Master Deliverable List \(MDL\)](#)

[Project Management Guide](#)

Target Audience for the Deliverables Expectations Matrix includes...

project teams	new designers	subject matter experts	traffic
consultants	design	design-builders	specialty firms

	Scoping	project management plan development	geometric design review	constructability review	pre-contract review	contract ready (final review)	Contract Ad and Award	Design phase Closure
1 Timeline actions and purpose	corridor sketch / planning study project profile informs scoping and design start; begin Basis of Design with initial baseline project need	~10% Identify team members • consultants, wsdot staff, or combination core team members • extended team members • roles and responsibilities project endorsement design criteria draft assumptions deliverable requirements project delivery method	~30% Design criteria final design decisions Design approval Design Manual Ch. 300 Basis of Design complete	~60% major design elements completed underground & overhead conflicts identified conflicts, utilities, drainage, etc. review constructability 3D modeling complete	~90% delivers substantially complete document to reviewers	100% Region PS&E review (typically 10 weeks), bids from contractors to construct the project.	WSDOT publicly solicits bids from contractors to construct the project.	Transition to construction bid letting
2 Project Management	corridor level vision	PMP & work plan [DBE goals] Project Kickoff Initiate & align worksheet! Baseline schedule Budget known Risk Management Plan Communication plan Change management plan Quality Plan (QA, QC, QV) Endorsement Executing work	Current project management plan (and work plan) – Capital Program Development & Management Office (CPDM) Manual, Design Manual 305; monitor & control (Quarterly Project Report)	Quality: Control – actions at the production levels to produce the desired quality and professional services. Assurance – actions to ensure prudent quality control procedures are in place.	Official closure and handoff Lessons learned recognized accomplishments organized end of design activities transition of work or staff documentation per retention requirements			
3 Cost Estimates	Basis of Estimate Preliminary cost estimate developed for Project Definition	updated estimate & basis Budget assumptions communicated Determine if project needs: Value Engineering and/or Risk Assessment updated estimate & basis	Begin item by item Project Estimate (update basis of estimate) F/W Project Funding Estimate completed	Estimate item quantities and unit costs. (update basis of estimate) updated estimate & basis Pay groups and pay items determined	Check that all items are included and correct. (update basis of estimate) Cost estimate completed with below the line items. Summary of quantities completed, item prices determined,	engineer's estimate at ad	Verify that all items are included and correct. (final basis of estimate) Cost estimate completed with below the line items. Summary of quantities completed, item prices determined,	
4 Environmental Review, Permitting, & Documentation	Identify and confirm level of required environmental documentation. Environmental Review Summary completed	Verify permits and documentation needed Environmental budget and schedule submittal Agreement on Area of Potential Affect for Section 106 and Action Area for ESA coordination with agencies Environmental surveys of project footprint Complete necessary Env docs and permits to complete Geotech work	Coordination with agencies NEPA/SEPA compliance documentation Environmental Permit Applications	Coordination with agencies NEPA/SEPA compliance documentation Environmental Permit Applications	Coordination with agencies NEPA/SEPA Compliance documentation Environmental Permit Applications	Coordination with agencies NEPA/SEPA Compliance documentation Environmental Permit Applications	Coordination with agencies NEPA/SEPA Compliance documentation Environmental Permit Applications	

		Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure
5	Cost Risk Estimating Management	concept sketch / planning study	~70%	Project Risk Assessment process steps are built into the project management plan, work schedule and scope of work. Review the Project Risk Management Guide; milestones for Scope, Schedule and Estimate are used to inform the timing of activities for project risk assessment. This includes updates. Establish milestones for cost risk assessment prep meetings and activities, workshop(s) and post workshop activities in the project schedule. Schedule Risk monitoring and control activities.	Status of project risks. Update analysis if needed.	~60% Status of project risks. Update analysis if needed.	~90% Status of project risks. Update analysis if needed.	Prepare summary of project risk status.
6	Value Engineering	Early determination of project needs for project risk assessment: Cost Risk Assessment, CRA or Cost Estimate Validation Process, CEVP.	Review the Value Engineering chapter of the Design Manual. Value Engineering is an effective process for ensuring Practical Design. Value Engineering activities are built into the project schedule.	Value Engineering workshop.	Implementation of Value Engineering recommendations.	Follow-up and follow-through of value engineering recommendations.	Prepare summary of value engineering recommendations as implemented into the final design.	
7	Pavement	Scoping Level Pavement Design Report completed, including: <ul style="list-style-type: none">o WSPMS/Historical Data/Maintenance Inputo Projected Traffic Type/Usageo Existing Conditions/Primary Deterioration<ul style="list-style-type: none">o Highway Activity Tracking System, HATSo PI One-Touch Policy	Scoping level Pavement Design reviewed Region materials Pavement Design Report requested Preliminary Pavement Type Selection Completed Field and Core investigation completed Draft Pavement Design Report completed	Draft Pavement Type Selection completed Draft Pavement Design Report approved by Region, (sent to Pavement Office for concurrence)	Pavement Type Selection submitted to Pavement Office for Final Approval Draft Pavement Design Report completed	Final Pavement Design Report with Region stamp and Pavement Office signed concurrence to Region for Plan Review	Pavement Repair quantities and locations reviewed with Construction PE/O for verification of field accuracy	

	Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award	Design phase Closure
	corridor sketch / planning study			pre-contract review	100%	bid letting	Transition to construction
Utilities and Railroad	Potential utility relocations identified Responsibility for costs established	Utilities within the project limits notified. Washington Utilities Transportation Commission (WUTC) permit application for railroad crossings submitted Utility As-Builts requested. Railroad (RR) issues identified. Relocation cost responsibility defined. Franchisee and permit documentation collected. Utility relocation strategy for project established.	Utility Conflict Report & Plan with as-built info, Preliminary Utility conflicts identified. Utility Object Relocation Record-UORR sent to Utilities. Project Overview Meet w/Utility Owners C & D completed. Determine need for Subsurface Utility Engineering, SUE Utility Quality Level A & B. Relocation plans/schedule request from Utilities. Franchise/Permit process initiated; cost recovery accounts initiated. Utility property rights verified. Railroad standard Construction Maintenance Agreement (CMA) obtained	Utility conflicts confirmed and relocation letters sent to Utilities. Utility relocation meeting held. Utility Relocation Plans and schedules obtained. Utility and railroad agreements completed. Utility Franchise/Permit obtained. Finalize utility agreements (costs responsibility estimate complete)	~60% ~90% Utility Relocation Plan information and specifications incorporated in PS&E. Letters of Understanding issued to Utilities requiring relocation. Utility, service, and railroad agreements completed. Utility relocation and schedule monitored and coordination completed. Construction and Maintenance Agreement completed.	100%	Utility relocation work completed or timeline established
Access – limited/managed	Define existing access status; managed access and/or limited access A choice to change current or planned access is to be consistent with the contextual information, desired performance targets, and mode priorities. DM 1103. Evaluate Access Master plan - determine most appropriate access control Document in BOD Section 3. Identify general project impacts to access.	Identify affected abutters for access report and hearings. Determine if an access hearing is required. Evaluate access connections and identify improvements. Limited access	Findings and Order Plan Appeal Period Resume Access hearing Access Report and Access Report Plan prehearing packet	New limited Right of Way Limited Access Plan			
Managed Access	Review grandfathered approaches and existing permitted approaches. Evaluate access connections and identify improvements. Is it appropriate to combine or close connections and reduce traffic conflicts?	Managed Access Control Permits in the RAMPS database, reviewed and updated. RAMPS = Roadway Access Management Permit System	Note: Managed Access connections are not noted on the Right-Of-Way plans. There is no Right-Of-Way plan change unless WSDOT requires Right-Of-Way.				

	Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure Transition to construction
10 Right-Of-Way Right of Way Manual, Chapter 6 Design Manual 5.10	Property required for a public facility, includes square footage, access rights, easements, and any property impacts.	Real Estate Services assists in minimizing right of way costs, defining route locations and acquisition areas, and determining potential problems and possible solutions.	Plan development: "red line R/W plan" R/W cost estimates made by Real Estate Services.	Confirm status of right of way acquisition. • Examine Title reports. • Add easements to right of way and limited access plan. • Obtain utility, railroad, haul road, detour routes, or other essential agreements. <i>Utilities Agreements Manual</i> and the <i>Agreements Manual</i> . • Plan right of way acquisition, disposal, and maintenance. • Plan easements and obtain permits (to accommodate activities outside of the right of way).	~60% Right-of-way acquisitions complete.	~90% 100%	
... Community Engagement	multimodal, multigenerational, multidisciplinary engagement concept team launch <i>get in/out, from region communications</i>	community engagement plan complete confirm need & context Design controls Alternatives Analysis preferred alternative Elements/Dimensions Identified Dimensioned	Investigate design concepts that incorporate community feedback	Community engagement ideas fully implemented into contract plans			Design documentation transferred to construction project office.
12 Design Documentation	Context Management Assessment Report (CMAR) complete BOD initiated	Section 1 and 2 of the BOD complete. Baseline and contextual needs including performance metrics and targets. Context determined. Section 3 and 4 in draft form circulated for concurrence.	All sections of BOD complete and BOD approved	If a separate Design Approval is necessary, it should be completed in this phase. Design Analysis completed.	Project Development Approval complete or combined Design Approval/Project Development Approval complete.	Design Documentation Package complete	
13 Roadway Geometrics and Plans	Project limits identified Affected alignments identified New versus existing alignment Target speed Preliminary design criteria established	Design criteria and parameters approved Preliminary footprint designed	Typical roadway section(s) completed; station to station roadway geometrics, surfacing type & depth, slope information, guardrail, vertical cut locations, and construction notes Mainline and major horizontal, & vertical alignments, and superelevations designed	All horizontal & vertical alignments & superelevations completed Design Analysis approved DDP updated as required Design compared to endorsed design criteria/ parameters	Final Plans for PS&E contract		

Project Development >	Scoping	project management plan development	geometric design review	constructability review	pre-contract review	contract ready (final review)	Contract Ad and Award	Design phase Closure
	corridor sketch / planning study				~60%	~90%	bidding	Transition to construction
14 Channelization and Pavement Marking Plans	Intersection Control Analysis (ICA) approved (if not already complete in scoping)	Roundabout Geometric Design Peer Review complete. Intersection Plans for Approval submitted for review. Signal permits completed. Striping material selected.	Design Analysis submitted and approved Intersection plans for approval complete	All plans completed Approved Channelization Plan verified for consistency with pavement marking plans and specifications				
15 Hydraulics & Water Quality see Temporary Erosion and Sediment Control (TESC)	Drainage needs identified in accordance with Maintenance and Regional Hydraulics	Design criteria identified Storm water Management requirements identified Water quality requirements identified Retrofit Cost-Effectiveness and Feasibility (RCEF) Analysis Confirm specific criteria for: - Fish Passage - Chronic Env Deficiency - Major Drainage - Bridge Scour/ replacement	Storm water Management strategies, including locations for treatment identified (hydraulic and water quality issues identified) Sensitive Area Documentation completed (Water Resource Inventory). Stormwater Management Strategy endorsed by region or HQ hydraulics engineer	60% check-in using Hydraulic Report Checklist TS&L of drainage facilities determined - Documentation of needs - Existing basins and flows for anticipated Threshold Discharge Areas - Identification of Minimum - Requirements from Highway Runoff Manual (HRM). Storm Water Report submitted to region for review and approval Hydraulic Report Submitted Preliminary Stormwater Mgmt options to identify RW needs completed Preliminary Hydraulics Design, i.e. stream design	Hydraulic Report Final approved/verified for consistency with plans and specifications Storm water details completed If applicable, transfer stormwater retrofit funds over to the I-4 Subprogram, Stormwater Retrofit Category Final Hydraulic Design, i.e. stream design			
16 Survey & Mapping	LiDAR or existing aerial photos or other preliminary information.	Project survey requirements finalized, including areas that may be outside roadway corridor improvements. Project survey control completed Cadastral survey performed. Topographic Survey complete.	Design level mapping completed Record of Survey completed and filed Right of Way plan completed and approved Relocation plan completed	Mapping of new roadway features completed Field review of proposed features completed	DNR Permits to Destroy Monuments obtained	Preliminary construction staking data completed		

Project Development >	Scoping	project management plan development	geometric design review	constructability review	pre-contract review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure Transition to construction
17 Structures (Bridges, Retaining Walls, Noise Walls, high mast lighting, sign structures) Also, refer to "Structural Submittal Expectations Matrix" .	Determine needed structure and/or geotech work. Square footage cost estimates of structures	Structural Input for Environmental Documentation and Permits Begin Coordination: project scope, preservation activities, construction staging, layout and span lengths, design constraints, seismic operational classification Submit: TS&L (when required)	~10% Structural Participation in Agency Coordination Agreements Finalize Scope of Work	~30% Refer to Deliverables in The Structural Matrix "Bridge Preliminary Plan"	~60% Refer to Deliverables in The Structural Matrix "Constructability Review Set"	~90% Refer to Deliverables in The Structural Matrix "PS&E Review Set"	100% Refer to Deliverables in The Structural Matrix "Signed PS&E Set"	
18 Illumination, Signals and ITS	Establish required light levels (roadway and pedestrian classification). Determine ITS needs and preliminary equipment locations.	Coordinate with signal operations for any proposed new or modified traffic signal systems. Signal operations will develop signal-phasing plans(s) as part of signal system analysis. Start speed study for existing intersections. Begin collection of as-built data for existing locations.	~10% Finalized Comment Resolution Form Approved Bridge Preliminary Plan End of Phase Document: Approved Bridge Preliminary Plan Coordinate with signal operations for any proposed new or modified traffic signal systems. Signal operations will develop signal-phasing plans(s) as part of signal system analysis. Start speed study for existing intersections. Begin collection of as-built data for existing locations.	~30% Box/vault, cabinet, and conduit layout complete. Wiring / network (fiber) diagram complete. Illumination Light Level Analysis complete. Signal phasing plan complete. Preliminary signal plan approved. Pole locations provided to design for coordination of grading and drainage. Confirm lateral bearing pressure design for poles. Wind load charts for signal standards Contact structural designer for poles mounted on structures. Determine preliminary utility connections (power or communications) and initiate coordination with serving utilities.	~60% All notes and schedules complete, including review and approval of supporting calculations. Supporting detail plans complete. Provide service agreement requests (power or communications) to utilities office for processing.	~90% Final plans complete. Service agreements complete.	100% Final plans complete. Service agreements complete.	

Project Development >		Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure
	complaint sketch / planning study	Support for TS&L	~70%	~60%	~90%	100%	Required Information	Transition to construction
²⁰ Geotechnical Recommendations	Scoping level cost estimate for project/workforce planning, based on project size, location, known elements & historical costs.	Submittal: TS&L (when required)	Required Information from Others: • PMP • Work Request • Scope of Work Agreement • Draft Schedule	Required Information from Others: • Project Site Data; ○ Mainline and major horizontal & vertical alignments ○ Typical roadway sections ○ TS&L of <u>all</u> Structures ○ Wall Site Data ○ Hydraulic/Storm water features	Required Information from Others: • Approved Bridge Preliminary Plan • Roadway sections • Draft Bridge Scour Recommendations • Survey Borehole locations • Field Exploration Plan & utility locates • Soils Data to Hydraulics • Geotechnical Information for Bridge Sub-Structure Design	Required Information from Others: • Final Hydraulic Design (FHD) • PS&E Review Set End of Phase Document: • Final Geotechnical Recommendations (Report/Memorandum)	Required Information from Others: • Decommissioning of wells	Project close out & transition to Construction support
²¹ Traffic Analysis Operations Analysis Interchange Justification Report (IJR) / Access Revision Report (ARR)	Basic traffic control strategies & alternatives identified. Projects of significance must have Traffic Management Plan (TMP) scoped.	• Scoping level • Operational analysis complete for alternatives consideration	Operations analysis scope determined • Traffic data collected • Perform Operations Analysis Intersection Control Analysis (ICA) approved (if not already complete in scoping)	Operations analysis complete. IJR/ARR complete	Assumptions and conclusions in Operations Analysis verified for consistency with design.	Final TMP completed.	TMP, including traffic control plans completed and associated specials approved	
²² Safety Analysis Crash Analysis Report (CAR)	Reference Safety Analysis Guide for what will be needed for safety analysis for the funding program. CAR is complete if funded from the Collision Reduction program.	Gather data necessary for Safety Analysis. Perform Safety Analysis	Safety Analysis complete.	Assumptions and conclusions in Safety Analysis verified for consistency with design.				

Project Development >	Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure Transition to construction
23 Signaling	corridor sketch / planning study	<ul style="list-style-type: none"> Contact Region Traffic Office to discuss scheduling, scope of project, and needed information for sign design Gather and deliver signing information to the Traffic Office 	<ul style="list-style-type: none"> Existing signs to reuse and relocate defined Existing sign inventory complete/include electrical items for sign lighting, flashing beacons, or variable/dynamic message signs) Potential conflicts between light standards, camera poles, and signal poles with signs identified Requests for sign structures submitted to HQ Bridge and Structures Preliminary Guide Sign Plan developed Preliminary Lump Sum Estimate calculated 	<ul style="list-style-type: none"> Visual standards for corridor coordinated with Landscape Architect Signing plans, notes, sign specifications completed Conflicts with illumination, camera poles, and/or signal features, drainage or utilities identified Coordination with luminaires on structures or walls identified and mounting/foundation details completed Updated Lump Sum Estimate Utility Agreement and Utility Relocation Requests submitted Sign layout complete, include overhead signs 	<ul style="list-style-type: none"> Updated Sign Design Plan Sheets (Sign Specification Sheets – Removal, Relocation, & Roadside Sign Structures; Sign Plans; Sign Details) Overhead Sign Structure Plan Sheets completed Update Lump Sum Estimate 		
24 Temporary Erosion and Sediment Control (TESC)		Preliminary TESC completed		<ul style="list-style-type: none"> TESC plan submitted to region for review and approval 	<ul style="list-style-type: none"> Final TESC approved, including site visit Construction Water Quality Monitoring Plan submitted 	<ul style="list-style-type: none"> Approved TESC letter transmitted to PS&E Erosion Control Plans and Notes completed 	
25 Specifications			<ul style="list-style-type: none"> Start writing specials for non-standard bid items. 	<ul style="list-style-type: none"> Specifications preliminary run list completed 	<ul style="list-style-type: none"> Specifications run list completed All special provisions submitted for review and approval. Specialty groups specifications and special provisions completed Pay groups and pay items determined 		

Project Development >		Scoping	project management plan development	geometric design review	constructability review	contract ready (final review)	Contract Ad and Award bid/letting	Design phase Closure Transition to construction
	comridor sketch / planning study					~60%	~90%	100%
Maintenance	Include nearest Maintenance Operations Area to ensure initial planning will not negatively affect maintenance operations after project completion.	Ensure initial planning will not negatively affect maintenance operations after project completion. Meet to discuss current Pavement, Utilities, Right-Of-Way, Hydraulics, Structures, and Safety related issues and those that may affect M&O budget after project completion.	Verify guardrail type does not have negatively impact maintenance after construction (will the type installed create longer repairs, exposure to traffic, etc?).	Review that previously discussed M&O items (Pavement, Utilities, Right-Of-Way, Hydraulics, Roadway Geometrics and Plans, Structures, and Safety items) have remained in the design.				

Internal Scope of Work Agreement

Focus on results and deliverables. People producing the deliverables choose method and are responsible for results.

This agreement is between **[ENTER PROJECT OFFICE NAME HERE]** and **[ENTER SPECIALTY GROUP NAME HERE]** for

Project: **[ENTER PROJECT NAME HERE]**

Project Description: (Describe the *project scope of work* the *project team* is assigned to perform.)

"[Type details here.]"

[INSTRUCTIONS: Use the project description/need statements from the Basis Of Design and/or the team mission from the Initiate and Align Worksheet. Describe the results the project will produce and when they will be accomplished.]

Specialty Group Scope of Work: (Describe the **work needed from the specialty group.**)

"[Type details here.]"

[INSTRUCTIONS: Describe the expectations from the specialty group.]

Schedule: (Identify **deliverables and due dates.**)

"[Type details here.]"

[INSTRUCTIONS: Identify deliverable milestone dates, major activities, durations, predecessors, successors, and constraints. The project office and specialty group agree on naming conventions and level of detail documented in the schedule. The level of effort may be established at the phase, group or deliverable level. Upon endorsement of the Project Management Plan the start, finish milestone dates and overall schedule is agreed.]

Work Requirements: (Identify **inputs from project team.**)

"[Type details here.]"

[INSTRUCTIONS: List items the specialty group requires from the project office or another specialty group to accomplish the above scope of work. Identify the party responsible for its delivery and when the items must be provided by; e.g. Bridge Site Data is required from the project office before Bridge and Structures can begin design work and provide an accurate estimate.]

Cost Estimate/Budget Development: (The **costs for the deliverables/activities produced by the specialty group.**)

"[Type details here.]"

[INSTRUCTIONS: Estimate the costs (planned value) with the same level of detail as agreed to with the project schedule. Include an Estimate at Completion, aging plan and appropriate work operation codes. In PMRS, the planned value is created by allocating either the project costs to the activity resources or expenses detail. This is accomplished by assigning a number of hours by role to specific activities or by assigning cost directly to the activity as an expense. Specialty groups and the project office agree on which method will be followed for this project.]

Risks, Assumptions and Constraints: (Identify **issues** that may influence decisions and ability to accomplish the work.)

"[Type details here.]"

[INSTRUCTIONS: Identify potential risks, constraints or assumptions that may affect the specialty group's ability to accomplish the work within the agreed upon project scope, schedule or budget.]

Resources: (identify available resources - human, financial, technical or organizational)

"[Type details here.]"

[INSTRUCTIONS: Identify the project office and specialty group points of contact and other resources to accomplish the desired results.]

Monthly Project Updates: (Status updates due no later than the last business day of each reporting month.)

"Enter day of month updates are due" of each month.

"[Type details here.]"

[INSTRUCTIONS: Provide status updates, include: a) name of the **deliverable/activity** (as defined in the project schedule); b) actual **start/finish dates**; c) **percent complete**, d) remaining duration or expected finish date; e) remaining costs or hours and f) an updated Estimate at Completion (EAC) and aging plan. Identify variances to this scope of work agreement. Communicate issues, risks or changes that have occurred or are emerging. Provide a "look ahead" (10, 30, 60 days, etc.).

Endorsement: (Identify appropriate authority to endorse this internal scope of work agreement and its inclusion in the PMP.)

Project Manager: "[Type name and phone number here.]"

Date Endorsed: Click here to enter a date.

Specialty Group: "[Type name and phone number here.]"

Date Endorsed: Click here to enter a date.

NOTE: This template offers a guide/tool for use to establish agreed to expectations between the project team and specialty group resources. Users can tailor to the specific needs for their project and requirements.