3RD. LAKE WASH. FLOATING BR. STAGE II

ROADWAY PONTOON : (DESIGN CALCULATION & STRUDL OUTPUT - TYPICAL SECTION @ FINAL CONDITION)

ROADWAY SLAB
EXTERIOR VERTICAL WALL
BOTTOM SLAB

BY. Y.M.T.

1

Vol 12 of 33

SR # 90 County KING CS # 1704

Bridge Name 3RD LAKE FLOATING BR PHASE II

Bridge # 90/25N Contract # 2647

Contents

Designed by Checked by

Archive Box # Vol. # 12

L-2340 6/93

3003151

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
BRIDGE & STRUCTURES BRANCH

Project 3rd Lake Fl. Bridge - Phase II Design Sheet No. ..... of ..... sheets

S.R. 90 Made by ..... Check by ..... Date ..... Supv. .....

Index for Calculation Volumes

Volume	By	Contents
1	R.L. Diemert	Longitudinal Pontoon Design
2		
3		
4		
5		
6	H.F. Hansen	Anchor Cable Geometry
7		Anchor Cable Forces → 2 Dimensional
8		Anchor Cable Forces → 3 Dimensional
9		Anchor Cable Forces → 3 Dimensional
10		Anchor Cable Walls
11		Longitudinal Pontoon Check
12	Y.M. Tam	Roadway (Deck) Pontoon Transverse Design
13	Y.M. Tam	Roadway (Deck) Pontoon Transverse Design
14	K.S. Koh	Pontoon A Design
15		Pontoon A Design
16		Pontoon E Review (Transv.)
17	H.J. Knoper	Anchor Cable and Strudl Data
18		Interior & End Wall Design, Elevated Pontoon Railing
19	A.W. Bruesch	Pontoon B&C Transv. Design
20		Strudl for Pontoon B&C Transv. Design
21	S. Thomas M. Sheikizadeh	Final Draft and Quantity calcs.
22		Pier Wall Design & Misc
23		Pontoon E&F 6" Depth Increase
24	H.F. Hansen & H.J. Knoper	Transv. Wind + Wave Loading → 2 Dimensional → Computer Data
25		→ 3
26		3
27		3
28		3

33003152

DOT FORM 232-007 REVISED 5/83 -636-

Sheet No.

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
BRIDGE & STRUCTURES BRANCH

Project 3rd Lake Fl. Br - Phase II Design Sheet No.....of.....sheets

S. R. 90 Made by..... Check by..... Date..... Supv.....

Index for Calculation Volumes

Volume	By	Contents
29	R.L. Smith	Superstructure Spans
30	R.L. Smith	Superstructure Spans
31	J.E.D/SGR	Superstructure Spans, Design Criteria
32		Dynamic Study By The Closten Associates, Inc.
33		Vol I → General
		Vol II → New I-90 Floating Bridge (3rd Lake)
		Vol III → Lacey V. Murrow Floating Bridge
		Vol IV → Evergreen Point Bridge

33003153

DOT FORM 232-007 REVISED 5/83 -636-

Sheet No.

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
BRIDGE & STRUCTURES BRANCH

Project 3rd Lake Fl. Bridge - Pontoon Design Sheet No. ..... of ..... sheets

S.R. 90 Made by ..... Check by ..... Date ..... Supv. .....

Index for Calculation Volumes

Volume	By	Contents
1	R.L. Diemert	Longitudinal Pontoon Design
2		
3		
4		
5		
6	H.F. Hansen	Anchor Cable Geometry
7		Anchor Cable Forces → 2 Dimensional
8		Anchor Cable Forces → 3 Dimensional
9		Anchor Cable Forces → 3 Dimensional
10		Anchor Cable Walls
11		Longitudinal Pontoon Check
12	Y.M. Tim	Roadway (Deck) Pontoon Transverse Design
13	Y.M. Tim	Roadway (Deck) Pontoon Transverse Design
14	K.S. Kob	Pontoon A Design
15		Pontoon A Design
16		Pontoon E Review (Transv.)
17	H. Hooper	Anchor Cable and Strudl Data
18		Interior & End Wall Design, Elevated Pontoon Railing
19	A.W. Bruesch	Pontoon B&C Transv. Design
20		Strudl for Pontoon B&C Transv. Design
21	S. Thomas / M. Sheikizadeh	Final Draft and Quantity Calcs.
22		Pier Wall Design & Misc
23		Pontoon E&F 6" Depth Increase

33003154

DOT FORM 232-007 REVISED 5/83 -636-

Sheet No.

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
BRIDGE & STRUCTURES BRANCH

Project 3RD LAKE WASH. FLOATING BR. STAGE II Sheet No. 1 A of 219 sheets
S. R. 90 Made by Y.N.T. Check by ..... Date 9-83 Supv. YTC/RTC

THIS CALCULATIONS DESIGN FOR ROADWAY PONTOONS E, F.
AND PORTION OF PONTOONS D & G, AS INDICATED BELOW:

1. ROADWAY SLAB, INCLUDED CANTILEVER SLABS
2. EXTERIOR WALLS (LONGITUDINAL)
3. BOTTOM SLAB

INDICATING
(1): MEMBER NO. 1 @ STRUCT. INPUT

TABLE OF CONTENTS:

	PAGE
A. ROADWAY SLAB.	
1. CANTILEVER SLABS (NORTH (1), SOUTH (7))	2 — 15
2. EXTERIOR CELL (2)	16 - 32
3. INTERIOR CELL (3)	33 - 59
4. INTERIOR CELL (4)	70 - 77
B. EXTERIOR VERTICAL WALL (5)	78 - 100
C. BOTTOM SLAB	
1. EXTERIOR CELL (14)	101 - 116
2. INTERIOR CELL (15)	117 - 132
D. TEMPORARY CONSTRUCTION CONDITION (ROADWAY SLAB)	
1. EXTERIOR CELL (2)	150 - 158
2. INTERIOR CELL (3)	159 - 165

33003155

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
BRIDGE & STRUCTURES BRANCH

Project 3RD LAKE WASH. FLOATING BR. STAGE II Sheet No. 1 B of 219 sheets
S. R. 90 Made by YMT Check by Date 9/82 Supv. YTC/RTS

	PAGE
E. P.S. TENDON STRESS DATA:	
1. ROADWAY SLAB.	123-128
2 BOTTOM SLAB	129-130
3. PONTOON D EXTERIOR VERT. WALL (LONGEST & SHORT TENDON).	131-134
4 PONTOON E EXTERIOR VERT. WALL (")	135-137
5 PONTOON P EXTERIOR VERT. WALL (")	138-141
6. PONTOON Q EXTERIOR VERT. WALL (")	142-143
7 PONTOON D INTERIOR VERT. WALL "	144-145
8 PONTOON E INTERIOR VERT. WALL "	146-147
9. TRANSV. WALL & TRANSITION SLAB TENDONS	148-149
F. STRUDL INPUT ASSUMPTIONS	166-223
G. STRUDL PRINT OUT & INPUT DATA (ATTACHED)	
1. YUM 2 — FINAL CONDITION	*
2* YUM 3 — TEMPORARY CONSTRUCTION CONDITION	COMPUTER INPUT & OUTPUT SEE BOOK 2
3.* YUM 4 — SECTION @ TRANSITION SLAB.	
H. TRANSITION SLAB @ PONTOON D	224-239

33003156